CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	88
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6: (G)Z *

DRAINAGE STRUCTURE SCHEDULE – 5

#	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L(OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE A, SPCL F & G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, SPCL F & G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	TYPE A, 7' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME AND LID TY 1 CL	FRAME AND GRATE TY 3	GRATE AND COVER TY 2B	GRATE TY 37	PRC FLARED END SECT: 12"	18"	24"	36"	72"	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HVY DUTY EXCELSIOR BLANKET	COMMENTS
~~186~~	~~MAC BLVD~~	~~850+95.00~~	~~73.20~~	~~R~~	~~603.25~~																											1										1									
~~187~~	~~MAC BLVD~~	~~850+95.00~~	~~90.30~~	~~L~~	~~603.25~~						1																																								
~~188~~	~~N/A~~																																																				
~~189~~	~~N/A~~																																																				
~~190~~	~~N/A~~																																																				
~~191~~	~~N/A~~																																																				
~~192~~	~~N/A~~																																																				
193	MAC BLVD	854+05.00	58.20	L	605.12		1																																														
194	MAC BLVD	854+05.00	7.30	L	606.05		1																																														
195	MAC BLVD	854+05.00	7.30	R	606.05		1																																														
196	MAC BLVD	854+05.00	46.20	R	605.36		1																																														
~~197~~	~~MAC BLVD~~	~~854+05.00~~	~~71.90~~	~~R~~	~~"F"~~																															1															
198	MAC BLVD	855+60.00	58.20	L	604.66		1																																														
199	MAC BLVD	855+60.00	7.30	L	605.59		1																																														
200	MAC BLVD	855+60.00	7.30	R	605.59		1																																														
201	MAC BLVD	855+60.00	46.20	R	604.90		1																																														
~~202~~	~~MAC BLVD~~	~~855+60.00~~	~~71.50~~	~~R~~	~~"F"~~																															1															
~~203~~	~~MAC BLVD~~	~~857+15.00~~	~~83.30~~	~~L~~	~~604.54~~						1																																								
204	MAC BLVD	857+15.00	58.20	L	604.19					1																																											
205	MAC BLVD	857+15.00	7.30	L	605.12					1																																											
206	MAC BLVD	857+15.00	7.30	R	605.12					1																																											
207	MAC BLVD	857+15.00	44.21	R	604.47					1																																											
~~208~~	~~MAC BLVD~~	~~857+15.00~~	~~70.50~~	~~R~~	~~604.54~~																					1																1									
209	MAC BLVD	858+10.00	58.20	L	603.91		1																																														
210	MAC BLVD	858+10.00	7.30	L	604.84		1																																														
211	MAC BLVD	858+10.00	7.30	R	604.84		1																																														
212	MAC BLVD	858+10.00	42.10	R	604.23		1																																														
~~213~~	~~MAC BLVD~~	~~858+10.00~~	~~70.10~~	~~R~~	~~"F"~~																															1															
214	MAC BLVD	858+90.00	55.59	L	603.77		1																																														
215	MAC BLVD	858+90.00	40.32	R	604.07		1																																														
216	MAC BLVD	859+00.00	54.99	L	603.78					1																																											
217	MAC BLVD	859+00.00	40.10	R	604.07					1																																											
~~218~~	~~MAC BLVD~~	~~859+00.00~~	~~69.90~~	~~R~~	~~"F"~~																															1															
219	MAC BLVD	859+70.00	50.79	L	604.01		1																																														
220	MAC BLVD	859+70.00	38.55	R	604.25		1																																														
~~221~~	~~MAC BLVD~~	~~859+70.00~~	~~69.30~~	~~R~~	~~"F"~~																															1															
~~222~~	~~MAC BLVD~~	~~861+00.00~~	~~73.50~~	~~L~~	~~600.5~~						1																																								
223	MAC BLVD	861+00.00	46.20	L	604.52					1																																											
224	MAC BLVD	861+00.00	35.66	R	604.73					1																																											
~~225~~	~~MAC BLVD~~	~~861+00.00~~	~~67.40~~	~~R~~	~~600.5~~																					1																1									
226	MAC BLVD	862+30.00	39.78	L	605.06		1																																														
227	MAC BLVD	862+30.00	34.20	R	605.17		1																																														
~~228~~	~~MAC BLVD~~	~~862+30.00~~	~~66.80~~	~~R~~	~~"F"~~																															1															
~~229~~	~~MAC BLVD~~	~~865+60.00~~	~~38.24~~	~~L~~	~~605.4494~~					1																																										

NOTE:
"X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -5
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6: (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE Mar-20-2008 08:59:01AM
DRAWN BY CLG
CHECKED BY JWM

LAYOUT	BLW	01/28/08
DRAWN	CLG	01/28/08
REVIEWED	BLW	01/28/08

Mar-20-2008 08:59:01AM
#FILE#

HANSON

© Copyright Hanson Professional Services Inc. 2008