CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	93
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

DRAINAGE STRUCTURE SCHEDULE – 10

#	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L(OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE A, SPCL F & G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, SPCL F & G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	TYPE A, 7' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME AND LID TY 1 CL	FRAME AND GRATE TY 3	GRATE AND COVER TY 2B	GRATE TY 37	PRC FLARED END SECT: 12"	18"	24"	36"	72"	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HVY DUTY EXCELSIOR BLANKET	COMMENTS
~~407~~	~~N/A~~																																																				
~~408~~	~~N/A~~																																																				
409	MAC BLVD	819+90.00	68.20	R	603.19		1																																														
410	MAC BLVD	819+90.00	62.20	L	603.23		1																																														
411	MAC BLVD	820+00.00	62.20	L	603.26					1																																											
412	MAC BLVD	820+00.00	9.70	L	604.40							1																																									
413	MAC BLVD	820+00.00	68.20	R	603.18																			1																													
~~414~~	~~MAC BLVD~~	~~820+00.00~~	~~67.00~~	~~R~~	~~599.84~~																								1													1									
415	MAC BLVD	823+00.00	64.20	L	604.18					1																																											
416	MAC BLVD	823+00.00	13.30	R	605.11					1																																											
417	MAC BLVD	823+00.00	61.43	R	604.27		1																																														
~~418~~	~~MAC BLVD~~	~~823+00.00~~	~~75.50~~	~~R~~	~~599.8~~																								1													1									
419	MAC BLVD	825+40.00	64.20	L	605.03					1																																											
420	MAC BLVD	825+40.00	13.30	R	605.96		1																																														
421	MAC BLVD	825+40.00	52.20	R	605.27		1																																														
~~422~~	~~MAC BLVD~~	~~825+40.00~~	~~71.75~~	~~R~~	~~"T"~~																																					1										
424	MAC BLVD	826+80.00	64.20	L	605.50		1																																														
427	MAC BLVD	826+80.00	52.20	R	605.75		1																																														
~~428~~	~~MAC BLVD~~	~~826+80.00~~	~~72.50~~	~~R~~	~~"T"~~																																					1										
429	MAC BLVD	828+20.00	59.61	L	606.07		1																																														
431	MAC BLVD	828+20.00	7.49	L	607.06				1																																												
432	MAC BLVD	828+20.00	52.20	R	606.22		1																																														
~~433~~	~~MAC BLVD~~	~~828+20.00~~	~~73.25~~	~~R~~	~~602.29~~																								1													1									
434	MAC BLVD	829+50.00	52.20	L	606.66		1																																														
436	MAC BLVD	829+50.00	9.70	L	607.46				1																																												
437	MAC BLVD	829+50.00	52.20	R	606.66		1																																														
~~438~~	~~MAC BLVD~~	~~829+50.00~~	~~73.50~~	~~R~~	~~"T"~~																																					1										
439	MAC BLVD	831+00.00	52.20	L	607.17		1																																														
440	MAC BLVD	831+00.00	9.70	L	607.97				1																																												
442	MAC BLVD	831+00.00	52.20	R	607.17		1																																														
~~443~~	~~MAC BLVD~~	~~831+00.00~~	~~73.75~~	~~R~~	~~"T"~~																																					1										
444	MAC BLVD	834+00.00	75.05	L	607.73		1																																														
445	MAC BLVD	834+00.00	13.30	L	608.88		1																																														
446	MAC BLVD	834+00.00	12.70	R	608.88		1																																														
447	MAC BLVD	834+00.00	52.20	R	608.17		1																																														
~~448~~	~~MAC BLVD~~	~~834+00.00~~	~~72.75~~	~~R~~	~~"T"~~																																					1										
449	MAC BLVD	834+75.00	63.42	L	608.20		1																																														
450	MAC BLVD	834+75.00	12.52	L	609.13		1																																														
451	MAC BLVD	834+75.00	12.52	R	609.13		1																																														
452	MAC BLVD	834+75.00	51.42	R	608.44		1																																														
~~453~~	~~MAC BLVD~~	~~834+75.00~~	~~72.00~~	~~R~~	~~"T"~~																																					1										
454	MAC BLVD	836+00.00	60.65	L	608.62		1																																														
455	MAC BLVD	836+00.00	9.75	L	609.55		1																																														
456	MAC BLVD	836+00.00	9.75	R	609.55		1																																														

NOTE:
"X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -10
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. — DRAWN BY CLG
DATE Mar-20-2008 08:59:27AM — CHECKED BY JWM

© Copyright Hanson Professional Services Inc. 2006

HANSON

Mar-20-2008 08:59:27AM
$FILE$

LAYOUT	BLW	01/28/08
DRAWN	CLG	01/28/08
REVIEWED	BLW	01/28/08