


FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	102
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; (G)Z *				

STORM SEWER SCHEDULE - 7

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A												TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6					
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"					
479	607.57	480	607.33																CONNECT TO EXISTING SEWER @ TOP OF SLOPE, SEE DETAIL	
486	594.47	488	594.20																	
492	599.60	498	599.01																	
496	599.80	496	596.40																	
496	596.40	497	596.08																	
497	594.25	466	584.47																	
491	601.89	492	601.65	5															CONNECT TO EXISTING SEWER @ TOP OF SLOPE, SEE DETAIL	
492	599.35	492	599.66																	
497	597.65	414	597.10		101															
497	597.65	504	597.80		180															
498	597.80	503	598.00		153															
498	597.80	418	597.10		88															
507	607.83	508	607.41	40																
508	607.41	477	606.98	44																
509	595.90	80	595.00		148															
510	601.06	509	595.90	33																
511	601.38	512	601.17	3																
512	601.17	513	600.39	77																
513	600.23	514	595.90	22																
514	595.90	84	595.00		148															
515	600.79	411	600.72	8																
516	600.45	517	600.38	8																
517	600.38	412	600.36	3																
518	600.43	412	600.36	8																
519	599.90	413	599.81	8																
520	601.00	101	600.90	8																
521	601.20	103	601.10	8																
522	602.10	419	602.03	8																
523	599.46	254	599.00		21															
524	600.99	250	600.86	8																
525	600.13	251	600.06	8																
526	601.03	527	600.73	81																
527	600.73	127	600.43		78															
528	601.40	530	601.28	18																
529	601.00	531	600.88	18																
530	601.28	531	600.88		65															
531	600.88	187	600.25		103															
532	601.53	415	601.20	37																
533	598.10	534	598.00	9																
534	598.00	497	597.65		21															
535	599.24	536	599.17	9																
536	599.17	504	597.80	21																
537	599.22	538	599.15	9																
538	599.15	503	598.00	19																
539	598.10	540	598.00	9																
540	598.00	498	597.80		20															
541	599.90	148	599.00																	
542	599.90	497	599.00																	
543	627.32	544	615.27													35				
546	601.33	526	601.03	70																
547	599.30	503	598.00		51															

NOTE:
 "X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -7
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY JWM
 DATE Mar-20-2008 08:25:48AM

