

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	104
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; (G)Z *				

PIPE CULVERT SCHEDULE

NOTE 1 -SET ON EXISTING PIPE

ROADWAY	STATION	UPSTREAM INVERT ELEV (FT)	DOWNSTREAM INVERT ELEV (FT)	TYPE 1 RCCP 18" ELLIPTICAL	TYPE 1 RCCP 24"	TYPE 1 RCCP 36"	TYPE 1 RCCP 48"	TYPE 6 RCCP 36"	RCCP 60" (SPECIAL)	TYPE 6 RCCP 72"	TYPE 2 RCCP 72"	PRECAST REINFORCED CONCRETE FLARED END SECTION ELLIPTICAL 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	PRECAST REINFORCED CONCRETE FLARED END SECTION 48"	PRECAST REINFORCED CONCRETE FLARED END SECTION 60"	PRECAST REINFORCED CONCRETE FLARED END SECTION 72"	MEDIAN INLET STD 604101	GRATING FOR CONCRETE FLARED END SECTION 36"	HEAVY DUTY EXCELSIOR BLANKET	TRENCH BACKFILL	
MACARTHUR	786+20.00	597.00	596.00					252	309					2						62	48	
MACARTHUR	790+20.00	592.00	591.00													2					70	63
MACARTHUR	794+20.00	598.50	598.00			302								2							62	45
MACARTHUR	800+30.00	599.64	599.57			166								2							62	
MACARTHUR	801+14.00	600.18	599.80			164								2							62	
MACARTHUR	815+00.00	598.50	598.50			202								2							62	38
RAMP A	21+40.00	594.00	593.60				116									2					64	57
RAMP B	25+00.00	589.00	587.00							191							2				76	6
RAMP D	52+00.00	597.20	597.00			120								4							124	24
REC DR	104+20.00	595.20	595.00			116								4							124	22
REC DR	125+25.00	596.50	594.50			60								2							62	11
I-72 LT	531+00.00					40								2							62	
I-72 LT	592+00.00	596.60	596.56		12								1								24	
I-72 RT	592+00.00	596.11	596.00		12								1								24	
I-72	592+00.00	NOTE 1																	1		36	
LINCOLNSHIRE	180+83.00	600.52	600.14	170									2								40	
LINCOLNSHIRE	180+80.00	600.52	600.14	177									2								40	
BORROW AREA-OUTLET		580.85	580.85								119								2		76	
ENTRANCE-MAG RT	770+31.00	594.92	594.64		44									2							48	
ENTRANCE-MAG LT	821+70.50	600.40	600.28	32									2								40	
ENTRANCE-REG DR LT	115+00.00	597.33	597.23	46									2								40	
ENTRANCE-REG DR RT	115+00.00	597.33	597.23	46									2								40	
ENTRANCE-REG DR LT	126+15.40	596.85	596.62	50									2								40	
BIKE PATH	12+13.00	599.65	599.60			26								2						2	62	6
BIKE PATH	34+00.00	600.00	598.36		47									2							48	3
BIKE PATH	42+60.00	598.50	598.50			21								2						2	62	7
BIKE PATH	49+06.00	600.40	600.28	32									2								40	
BIKE PATH	83+05.00	600.20	600.00			55								2							48	3
PARKING LOT ENT. SOUTH		599.70	599.65	19									2								40	
PARKING LOT ENT. NORTH		602.10	601.90	28									2								40	
-TOTALS-				600	115	1272	116	252	309	191	119	18	6	28	2	2	4	1	16	1680	332	

NOTE:
 "X" ITEMS INDICATE DRAINAGE STRUCTURES CONSTRUCTED IN PRIOR GRADING & STRUCTURES CONTRACT SHOWN FOR INFORMATION ONLY.

LAYOUT CLG 09/17/07
 DRAWN CLG 09/17/07
 REVIEWED JMW 03/12/08
 Mar-20-2008 08:25:34AM
 \$FILES*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PIPE CULVERT SCHEDULE
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
 HORIZ. _____
 DATE Mar-20-2008 08:25:34AM

DRAWN BY CLG
 CHECKED BY JMW