

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	425	378
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

3 OF 50
 • FAI 72 (I-72) AND FAU 8071 (MACARTHUR BOULEVARD)
 •• SECTION (84-9) RS-6; (G)Z

BILL OF MATERIALS

PAY CODE	DESCRIPTION	UNIT	QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	1.5
20200100	EARTH EXCAVATION	CU YD	7207
20400100	BORROW EXCAVATION	CU YD	2455
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2339
25000200	SEEDING, CLASS 2	ACRE	9.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	812
	PHOSPHORUS FERTILIZER NUTRIENT	POUND	812
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	812
25100115	MULCH, METHOD 2	ACRE	9.02
25100630	EROSION CONTROL BLANKET	SQ YD	900
28000300	TEMPORARY DITCH CHECKS	EACH	44
28000400	PERIMETER EROSION BARRIER	FOOT	12645
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	13500
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	95
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	2255
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	5370
54210300	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 15"	FOOT	204
54210309	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 24"	FOOT	66
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4
54214920	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 15"	EACH	8
54214929	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 24"	EACH	4
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	57
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	142
* 55028900	STORM SEWERS, TYPE 5, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS V 48"	FOOT	210
* 60247900	JUNCTION CHAMBER, SPECIAL	EACH	1
72000100	SIGN PANEL - TYPE 1	SQ FT	98
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	30
* K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1
XX004801	BITUMINOUS BIKE PATH REMOVAL	SQ YD	285
* XX006669	DROP GATE, SPECIAL	EACH	8
*	SHAPING AND GRADING TRAILWAY	UNIT	126

PLOT DATE = 11/04/08 11:40:00AM
 PLOT SCALE = 1/8" = 1'-0"
 PLOT SHEET = 213 / 213
 USER NAME = jng@hntb.com

REVISIONS	
NAME	DATE



Cedar Rapids, IA \ Iowa City, IA \ Des Moines, IA
 Moline, IL \ Bloomington, IL \ Chicago, IL
 SHIVE HATTERY, INC. 2308 BAYLAND DRIVE BLOOMINGTON, ILLINOIS 61710
 PHONE (309) 668-8888 FAX (309) 668-8888
<http://www.shive-hattery.com>
 ILLINOIS FIRM NUMBER 184-000024

ILLINOIS DEPARTMENT OF TRANSPORTATION

LEGACY POINTE SHARED USE PATH

BILL OF MATERIALS

SCALE: VERT. NONE DRAWN BY: JAB
 DATE: 3/6/08 CHECKED BY: DWS