

LOCATION OF WORK				NHS 80% FEDERAL 20% STATE	STP 80% FEDERAL 20% STATE	NHS 80% FEDERAL 20% STATE	NHS 80% FEDERAL 10% STATE 10% CITY	NHS 80% FEDERAL 13.33% STATE 6.67% CITY	STP 80% FEDERAL 10% STATE 10% CITY	STP 80% FEDERAL 13.33% STATE 6.67% CITY	STP 80% FEDERAL 10% STATE 10% COUNTY	NHS 80% FEDERAL 10% STATE 5% CITY	NHS 80% FEDERAL 10% STATE 10% CITY
URBAN				ROADWAY NORTH OF I-72	ROADWAY SOUTH OF I-72	SW PLAZA DR.	SIGNALS NORTH OF I-72	SIGNALS NORTH OF I-72 SW PLAZA DR.	SIGNALS SOUTH OF I-72 REC. DR. MATHERS RD	SIGNALS SOUTH OF I-72 PANTHER CR. DR.	SIGNALS SOUTH OF I-72 WOODSIDE RD.	5% SOUTHERN VIEW SIGNALS 6TH ST @ LINTON	SIGNALS 6TH ST. @ APPLE ORCHARD
				SEE NOTE 1				SEE NOTE 2					
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000-1A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3						1				1
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10				2	2				3	3
88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1										1
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1					1					
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1					1					
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	2				2						
88040320	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-4 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	2				2						
88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2				2						
88040332	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1									1	
88040355	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2									1	1
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4				4						
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2				2						
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	79				31	13				18	17
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6				6						
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1					
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	5				3		2				
89501100	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER	EACH	1					1					
89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1						1				
89502200	MODIFY EXISTING CONTROLLER	EACH	3				1					1	1
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,604				1,198	1,406					
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1,269				97		489	634			49
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	9				3	1	1	1	1	1	1
89502380	REMOVE EXISTING HANDHOLE	EACH	10					10					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	18				3	6	1			4	4
X0301183	GEOMETRICALLY PROGRAMMED LOUVER	EACH	30				12	6				6	6
X0320635	TWIN TENON, STEEL	EACH	2				2						

*

*SPECIALTY ITEMS

CUMMINS ENGINEERING CORPORATION		JOB - 2200
FILE - sht-500.dgn		DESIGNED - NAK
FILE NAME - C:\Projects\4652204\Cummins_fina\46728	USER NAME - laughlin	REVISIONS -
FILE - sht-500.dgn	DRAWN - AJH	REVISIONS -
PLOT SCALE = 100,0000 / IN.	CHECKED - NAK	REVISIONS -
PLOT DATE = Mar-20-2008 07:16:03AM	DATE - 3/15/2008	REVISIONS -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	
---	--

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	2-2(RS) & 3-1, 2(RS-10, TS-5)	SANGAMON	181	10
CONTRACT NO. 72889				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				