

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
					TYPE 1, 8" SQ YD	TYPE 2, 8" SQ YD	TYPE 3, 8" SQ YD	TYPE 4, 8" SQ YD			
NB IL 4 - PASSING LANE											
273	639+20	18	6	12.0		12.0			66	12.0	
274	631+65	6	6	4.0	4.0			42	4.0		
275	628+80	6	12	8.0		8.0		72	8.0		
276	627+80	6	6	4.0	4.0			42	4.0		
277	623+30	6	6	4.0	4.0			42	4.0		
278	623+00	6	6	4.0	4.0			42	4.0		
279	622+50	6	6	4.0	4.0			42	4.0		
280	621+90	8	6	5.3		5.3		46	5.3		
281	621+70	6	24	16.0			16.0	132	16.0		
282	621+20	12	6	8.0		8.0		54	8.0		
283	620+90	18	6	12.0		12.0		66	12.0		
284	620+70	6	6	4.0	4.0			42	4.0		
285	620+40	6	6	4.0	4.0			42	4.0		
286	619+90	6	6	4.0	4.0			42	4.0		
287	619+00	8	6	5.3		5.3		46	5.3		
288	616+80	6	6	4.0	4.0			42	4.0		
289	614+60	10	6	6.7		6.7		50	6.7		
290	613+90	10	6	6.7		6.7		50	6.7		
291	611+70	6	6	4.0	4.0			42	4.0		
292	610+50	6	6	4.0	4.0			42	4.0		
293	595+80	6	12	8.0		8.0		72	8.0		
294	501+50	6	6	4.0	4.0			42	4.0		
295	488+00	6	6	4.0	4.0			42	4.0		
296	487+80	6	6	4.0	4.0			42	4.0		
297	458+00	6	12	8.0		8.0		72	8.0		
298	453+10	6	6	4.0	4.0			42	4.0		
299	452+90	6	6	4.0	4.0			42	4.0		
300	412+20	6	12	8.0		8.0		72	8.0		
301	404+50	6	12	8.0		8.0		72	8.0		
302	396+20	6	12	8.0		8.0		72	8.0		
303	385+30	6	12	8.0		8.0		72	8.0		
304	380+80	6	12	8.0		8.0		72	8.0		
305	380+40	8	12	10.7		10.7		76	10.7		
306	376+60	6	12	8.0		8.0		72	8.0		
307	373+00	6	12	8.0		8.0		72	8.0		
308	370+60	6	12	8.0		8.0		72	8.0		
309	370+40	6	12	8.0		8.0		72	8.0		
310	366+00	6	12	8.0		8.0		72	8.0		
TOTAL					64.0	170.7	16.0	0.0	2,194	250.7	0

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS B			SAW CUTS FOOT	PAVEMENT FABRIC SQ YD	DOWEL BARS EACH
					TYPE 1, 8" SQ YD	TYPE 2, 8" SQ YD	TYPE 3, 8" SQ YD			
NB LEFT TURN LANE TO GREENBRIAR										
1	378+00	6	14	9.3		9.3		40	9.3	12
1	10+00	6	16	10.7		10.7		44	10.7	12
SB RIGHT TURN LANE TO ILES										
2	391+24	8	8	7.1		7.1		32	7.1	16
2	7+15	18	12	24.0			24.0	60	24.0	36
3	7+50	18	12	24.0			24.0	60	24.0	36
4	7+50	6	12	8.0		8.0		36	8.0	12
NB LEFT TURN LANE TO ILES										
1	396+00	6	14	9.3		9.3		40	9.3	12
SOUTHWEST PLAZA DR										
7	8+30	6	12	8.0		8.0		36	8.0	12
8	8+30	6	12	8.0		8.0		36	8.0	12
9	8+50	10	16	17.8			17.8	52	17.8	20
SB LEFT TURN LANE TO WABASH AVE										
7	417+75	6	16	10.7		10.7		44	10.7	12
8	417+75	10	6	6.7		6.7		32	6.7	20
NB LEFT TURN LANE TO WABASH AVE										
9	421+60	8	12	10.7		10.7		40	10.7	16
WABASH AVE										
10	513+20	6	12	8.0		8.0		36	8.0	12
11	513+60	12	12	16.0			16.0	48	16.0	24
12	515+88	6	6	4.0	4.0			24	4.0	12
TOTAL					4.0	96.5	81.8	660	182.3	276

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
					TYPE 1, 8" SQ YD	TYPE 2, 8" SQ YD	TYPE 3, 8" SQ YD	TYPE 4, 8" SQ YD			
SB RIGHT TURN LANE TO GREENBRIAR											
311	371+75	6	6	4.0	4.0			42	4.0		
312	372+70	10	6	6.7		6.7		50	6.7		
313	372+90	14	6	9.3		9.3		58	9.3		
314	373+10	8	14	12.4		12.4		86	12.4		
315	373+25	6	6	4.0	4.0			42	4.0		
316	373+90	8	14	12.4		12.4		86	12.4		
317	374+00	12	14	18.7			18.7	94	18.7		
GREENBRIAR DR.											
313	11+00	50	12	66.7			66.7	160	66.7	25	
314	11+00	12	18	24.0			24.0	114	24.0		
NB RIGHT TURN LANE TO ILES AVE											
415	397+50	16	10	17.8			17.8	82	17.8		
316	400+20	20	6	13.3		13.3		70	13.3	10	
SB RIGHT TURN LANE TO LINDBURGH BLVD											
317	453+00	6	12	8.0		8.0		72	8.0		
NB RIGHT TURN LANE TO LINDBURGH BLVD											
318	459+00	6	6	4.0	4.0			42	4.0		
TOTAL					12.0	62.1	60.5	66.7	998	201.3	35

CUMMINS ENGINEERING CORPORATION		JOB - 2200
FILE NAME =		FILE - sht-schedule.dgn
USER NAME = laughton1	DESIGNED - NAK	REVISED -
PROJECT = c:\projects\d652204\cummins_final\d672889\sh-schedule.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = Mar-18-2008 12:35:52PM	DATE - 2/8/2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	2-(IRS) & 3-1, 2(IRS-10, TS-5)	SANGAMON	181	34
CONTRACT NO. 72889				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				