

PAVEMENT REMOVAL		
LOCATION		SQ YD
STAGE 1		
STA 438+28.00	TO STA 440+68.00	136
STAGE 2		
STA 435+38.97	TO STA 435+63.18	26
STA 436+09.00	TO STA 442+65.43	924
STAGE 3		
STA 435+89.75	TO STA 439+00.00	93
TOTAL		1,179

HOT MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH		
LOCATION		SQ YD
STA 365+00.00	TO STA 369+98.96	555
STA 370+00.00	TO STA 375+37.80	598
TOTAL		1,153

CONCRETE MEDIAN SURFACE REMOVAL		
LOCATION		SQ FT
SB IL 4 TO EB GREENBRIAR		
STA 374+02.00	TO STA 375+25.90	559
STA 374+30.00	TO STA 375+75.00	839
GREENBRIAR SIDEWALK		
59' RT STA 376+57		8
57' RT STA 376+62		8
4' LT STA 376+55		59
5' LT STA 376+58		19
63' LT STA 376+55		17
61' LT STA 376+59		12

ILES SIDEWALK		
LOCATION		SQ YD
63' RT STA 396+08		10
64' RT STA 396+13		5
10' LT STA 396+10		12
10' LT STA 396+15		12
68' LT STA 396+15		14
68' LT STA 396+21		9

SB IL 4 TO EB ILES AVE		
LOCATION		SQ YD
STA 389+40.00	TO STA 395+72.54	2,494
STA 390+52.93	TO STA 395+32.92	2,001

SB IL 4 TO EB WABASH AVE.		
LOCATION		SQ YD
STA 415+56.65	TO STA 415+68.65	36

NB IL 4 TO WB WABASH AVE		
LOCATION		SQ YD
STA 420+66.70	TO STA 420+72.70	18

SOUTHWEST PLAZA DR		
LOCATION		SQ YD
STAGE 1		
STA 435+75.00	TO STA 439+57.00	3,915

STAGE 2		
LOCATION		SQ YD
STA 435+95.00	TO STA 438+35.00	2,391
STA 435+50.00	TO STA 435+68.00	158
STA 436+59.40	TO STA 438+10.30	1,069

NB IL 4 TO WB LINDBERGH DR		
LOCATION		SQ YD
STA 457+98.61	TO STA 459+47.20	1,323

LINDBERGH SIDEWALK IMPROVEMENT		
LOCATION		SQ YD
72' LT STA 457+12		187
10' RT STA 456+94		241
74' RT STA 456+97		214

SB IL 4 TO EB RECREATION DR		
LOCATION		SQ YD
STA 512+57.12	TO STA 517+11.15	3,585
STA 512+57.64	TO STA 517+29.00	4,936

NB IL 4 TO WB MATHERS RD		
LOCATION		SQ YD
STA 518+34.00	TO STA 521+10.73	3,891
STA 518+34.17	TO STA 519+62.18	930

NB IL 4 TO WB PANTHER CREEK DR		
LOCATION		SQ YD
STA 547+63.00	TO STA 550+27.17	3,506
STA 547+63.00	TO STA 548+81.10	836

INLETS TO BE ADJUSTED		
LOCATION		SQ YD
TRAFFIC SIGNALS		357
CURB REPAIR		78
TOTAL		34,277

COMBINATION CURB AND GUTTER REMOVAL			
LOCATION			FOOT
SB IL 4 TO EB GREENBRIAR			
STA 374+02.00	TO STA 375+25.90		248
STA 374+30.00	TO STA 375+72.00		284
GREENBRIAR SIDEWALK			
61' RT STA 376+60			21
56' RT TO STA 376+60			9
4' RT STA 376+57			7
14' LT STA 376+56			45
57' LT STA 376+57			33
67' LT STA 376+62			6

ILES SIDEWALK			
LOCATION			FOOT
67' RT STA 396+12			17
60' RT STA 396+10			14
2' LT STA 396+12			20
16' LT STA 396+12			20
58' LT STA 396+17			20
72' LT STA 396+22			20

SB IL 4 TO EB ILES AVE			
LOCATION			FOOT
STA 389+31.74	TO STA 394+75.04		1,087
STA 390+36.42	TO STA 395+35.57		998

SB IL 4 TO EB WABASH AVE.			
LOCATION			FOOT
STA 415+56.65	TO STA 415+68.65		24

NB IL 4 TO WB WABASH AVE			
LOCATION			FOOT
STA 420+66.70	TO STA 420+72.70		12

SOUTHWEST PLAZA DR			
LOCATION			FOOT
STAGE 1			
STA 435+75.00	TO STA 439+57.00		537

STAGE 2			
LOCATION			FOOT
STA 435+95.00	TO STA 438+35.00		256
STA 434+75.90	TO STA 6+31.68		352
STA 435+50.00	TO STA 435+68.00		56
STA 436+59.40	TO STA 438+50.00		350

NB IL 4 TO WB LINDBERGH DR			
LOCATION			FOOT
STA 457+99.81	TO STA 459+47.20		295

LINDBERGH SIDEWALK IMPROVEMENT			
LOCATION			FOOT
88' LT STA 456+95			8
76' LT STA 457+08			8
65' LT STA 457+10			8
2' LT STA 456+93			8
24' RT STA 456+94			8
66' RT STA 456+94			8
76' RT STA 456+92			8
92' RT STA 456+75			8

NB IL 4 AT RAMP C & D			
LOCATION			FOOT
STA 485+75.95	TO STA 486+31.50		77

SB IL 4 TO EB RECREATION DR			
LOCATION			FOOT
STA 512+57.12	TO STA 517+11.15		908
STA 512+55.25	TO STA 517+29.00		948

NB IL 4 TO WB MATHERS RD			
LOCATION			FOOT
STA 518+34.00	TO STA 521+14.10		560
STA 518+32.17	TO STA 519+62.18		260

NB IL 4 TO WB PANTHER CREEK DR			
LOCATION			FOOT
STA 547+63.00	TO STA 550+31.00		536
STA 547+60.90	TO STA 548+81.10		239

INLETS TO BE ADJUSTED			
LOCATION			FOOT
TOTAL			312
TOTAL			8,635

PAVED SHOULDER REMOVAL				
LOCATION		WIDTH		SQ YD
STAGE 1				
STA 435+79.00	TO STA 438+28.00	8		222
STA 438+28.00	TO STA 439+33.00	7	TO 3	59
STA 433+85.15	TO STA 435+59.80	6		117

STAGE 2				
LOCATION		WIDTH		SQ YD
STA 426+95.74	TO STA 429+82.37	10		319
STA 429+82.84	TO STA 430+95.34	9	TO 4	82
STA 430+95.34	TO STA 432+35.07	4		63
STA 436+59.40	TO STA 438+19.52	8		143
STA 438+19.52	TO STA 440+76.67	6		172
STA 438+50.00	TO STA 442+65.43	4		185
STA 442+65.43	TO STA 444+86.71	6		148
TOTAL				1,510

MEDIAN REMOVAL			
LOCATION			SQ FT
SB IL 4 TO EB GREENBRIAR DR			
STA 374+04.70	TO STA 374+30.00		111
STA 375+25.90	TO STA 375+53.00		73

SB IL 4 TO EB WABASH AVE			
LOCATION			SQ FT
STA 414+50.85	TO STA 415+56.65		709

NB IL 4 TO WB WABASH AVE			
LOCATION			SQ FT
STA 420+72.70	TO STA 421+72.85		601

SOUTHWEST PLAZA DR			
LOCATION			SQ FT
STAGE 1			
STA 439+57.60	TO STA 439+82.00		79

NB IL 4 TO WB LINDBERGH DR			
LOCATION			SQ FT
STA 458+25.00	TO STA 461+41.18		1175

TOTAL			
LOCATION			SQ FT
TOTAL			2,748

CURB AND GUTTER REPAIR				
LOCATION	COMBINATION CURB AND GUTTER REMOVAL & REPLACEMENT	CONCRETE MEDIAN SURFACE 4"	MEDIAN SURFACE REMOVAL	FOOT
GREENBRIAR DR		6		
NW ISLAND				
LT STA 8+20				
CTR MEDIAN CL STA 376+00 @ TY 15 CASTING		2		
CTR MEDIAN NB LTL GREENBRIAR @ TY 15 CASTING 376+65		4		
CTR MEDIAN SB LT STA 377+15 @ TY 15 CASTING		2	24	24
LT STA ILES 7+14 TO 7+24		10		
LT STA WABASH LTL 415+20 @ TY 15 CASTING		4		
LT STA WABASH LTL 416+20 @ TY 15 CASTING		5		
RT STA WABASH AVE LTL 417+70		10		
LT STA 458+20 TO 458+25 LINDBERGH DR			30	30
RT STA 9+35 SW ISLAND LINDBERGH DR		24	24	
LT STA 10+00 CL MEDIAN LINDBERGH DR @ TY 15		5		
TOTAL		48	78	78

SIDEWALK REMOVAL				
LOCATION				SQ FT
GREENBRIAR RD				
95' LT STA 376+76			30	
65' LT STA 376+55			19	
57' RT STA 376+58			81	
78' RT STA 376+75			57	
CL STA 375+88			62	

PCC SURFACE REMOVAL - VARIABLE DEPTH				
LOCATION		WIDTH		SQ YD
IL 4				
STA 453+82.00	TO STA 454+30.00	6		32
STA 461+13.00	TO STA 461+42.00	4		13
STA 574+37.00	TO STA 574+85.00	4		22
STA 580+93.00	TO STA 581+42.00	4		22
TOTAL				463

SOUTHWEST PLAZA DR				
LOCATION		WIDTH		SQ YD
STA 9+07.00	TO STA 9+29.00	4		10
TOTAL				99

PIPE UNDERDRAIN REMOVAL			
LOCATION			FOOT
STAGE 2			
STA 427+11.80	TO STA 432+35.07		583
STA 436+09.00	TO STA 439+25.00		316
STA 438+20.00	TO STA 444+86.71		703
TOTAL			1,602

LONGITUDINAL JOINT REPAIR				
LOCATION				FOOT
SB IL 4				
STA 377+00.00	TO STA 377+44.00			44
STA 395+85.00	TO STA 396+65.00			80
STA 414+00.00	TO STA 416+25.00			225
STA 432+00.00	TO STA 433+50.00			150
STA 434+00.00	TO STA 437+00.00			300
STA 437+00.00	TO STA 437+30.00			30
STA 442+20.00	TO STA 442+50.00			30
STA 454+50.00	TO STA 456+50.00			200
STA 456+75.00	TO STA 458+20.00			245
STA 507+50.00	TO STA 507+65.00			15
STA 549+80.00	TO STA 550+40.00			60
STA 570+60.00	TO STA 572+20.00			160