

GENERAL NOTES:

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. NO EXCAVATION ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD ANY EXCAVATION BE REQUIRED, J. U. L. I. E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE - (800) 892-0123.
3. ALL PROPOSED PAVEMENT MARKINGS SHALL BE PREFORMED PLASTIC IN NATURE AND SHALL CONFORM TO THE DISTRICT 6 PAVEMENT MARKING STANDARDS.
4. ALL CONFLICTING EXISTING STRIPING WILL BE REMOVED.
5. ALL PAVEMENT MARKINGS SHALL BE VERIFIED BY RESIDENT/FIELD ENGINEER PRIOR TO THEIR PLACEMENT.
6. EXISTING PAVEMENT DAMAGED DUE TO THE CONTRACTOR'S OPERATIONS, NOT OTHERWISE NECESSARY TO REPLACE, SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.

INDEX OF SHEETS:

1. COVER SHEET
2. GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. TRAFFIC SIGNAL LEGENDS
5. TRAFFIC SIGNAL LAYOUT
6. CABLE DIAGRAM

LIST OF STANDARDS:

- 000001-05
- 001006
- 424001-05
- 606001-03
- 701101-01
- 701106-01
- 701701-05
- 701901
- 857001
- 878001-06
- 880006

DISTRICT SIX	
EXAMINED <u>March 4</u> 20 <u>08</u>	
<i>Louis J. Hoare</i>	
OPERATIONS ENGINEER	
EXAMINED <u>FEB 27</u> 20 <u>08</u>	
<i>W. B. J.</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED <u>FEB 27</u> 20 <u>08</u>	
<i>W. B. J.</i>	
PROGRAM DEVELOPMENT ENGINEER	