

PATCHING SCHEDULE

CONTRACT: 72B92
SHEET 5 OF 5

APPROX. STA	LOCATION	LENGTH (FT)	WIDTH (FT)	CL A PATCHES TY II, 10-1/2" (SQ YD)	CL A PATCHES TY II, 12-1/4" (SQ YD)	CL A PATCHES TY III, 12-1/4" (SQ YD)	CL A PATCHES TY IV, 12-1/4" (SQ YD)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)	SAW CUTS (FT)
214+035	SBDL	6	12	8.0					8.0	60
214+109	SBDL	6	12	8.0					8.0	60
214+155	SBDL	6	12	8.0					8.0	60
214+377	SBDL	6	12	8.0					8.0	60
215+121	SBDL	6	12	8.0					8.0	60
215+249	SBDL	6	12	8.0					8.0	60
215+326	SBDL	6	12	8.0					8.0	60
215+472	SBDL	6	12	8.0					8.0	60
217+909	SBDL	6	12		8.0				8.0	60
217+915	SBDL	6	12		8.0				8.0	60
218+620	SBDL	6	12		8.0				8.0	60
218+626	SBDL	6	12		8.0				8.0	60
218+693	SBDL	6	12		8.0				8.0	60
219+550	SBDL	6	12		8.0				8.0	60
219+611	SBDL	6	12		8.0				8.0	60
219+753	SBDL	24	12				32.0	11	32.0	96
219+772	SBDL	6	12		8.0				8.0	60
219+855	SBDL	6	12		8.0				8.0	60
219+862	SBDL	12	12			16.0			16.0	72
220+046	SBDL	12	12			16.0			16.0	72
220+217	SBDL	6	12		8.0				8.0	60
220+227	SBDL	6	12		8.0				8.0	60
220+600	SBDL	6	12		8.0				8.0	60
220+639	SBDL	18	12			24.0			24.0	84
220+669	SBDL	12	12			16.0			16.0	72
220+750	SBDL	24	12				32.0	11	32.0	96
220+820	SBDL	12	12			16.0			16.0	72
221+204	SBDL	6	12		8.0				8.0	60
221+308	SBDL	24	12				32.0	11	32.0	96
221+344	SBDL	6	12		8.0				8.0	60
221+419	SBDL	24	12				32.0	11	32.0	96
221+576	SBDL	6	12		8.0				8.0	60
221+719	SBDL	6	12		8.0				8.0	60
221+832	SBDL	24	12				32.0	11	32.0	96
221+910	SBDL	12	12			16.0			16.0	72
221+921	SBDL	12	12			16.0			16.0	72
222+530	SBDL	6	12		8.0				8.0	60
222+542	SBDL	6	12		8.0				8.0	60
223+241	SBDL	6	12		8.0				8.0	60
223+271	SBDL	6	12		8.0				8.0	60
223+340	SBDL	48	12				64.0	23	64.0	144
223+352	SBDL	6	12		8.0				8.0	60
223+700	SBDL	6	12		8.0				8.0	60
223+782	SBDL	18	12			24.0			24.0	84
223+968	SBDL	6	12		8.0				8.0	60
224+063	SBDL	6	12		8.0				8.0	60
224+354	SBDL	6	12		8.0				8.0	60
224+466	SBDL	6	12		8.0				8.0	60
224+941	SBDL	6	12		8.0				8.0	60
224+949	SBDL	24	12				32.0	11	32.0	96
224+955	SBDL	6	12		8.0				8.0	60
225+225	SBDL	6	12		8.0				8.0	60
225+417	SBDL	6	12		8.0				8.0	60
226+490	SBDL	24	12				32.0	11	32.0	96
226+573	SBDL	6	12		8.0				8.0	60
227+741	SBDL	6	12		8.0				8.0	60
215+121	SBPL	6	12	8.0					8.0	60
218+620	SBPL	6	12		8.0				8.0	60
218+626	SBPL	6	12		8.0				8.0	60
218+693	SBPL	6	12		8.0				8.0	60
222+530	SBPL	6	12		8.0				8.0	60
223+968	SBPL	6	12		8.0				8.0	60
224+063	SBPL	6	12		8.0				8.0	60
224+354	SBPL	6	12		8.0				8.0	60
224+466	SBPL	6	12		8.0				8.0	60
TOTALS:				72.0	320.0	144.0	288.0	100	824.0	4356
+ 10% *:				7.2	32.0	14.4	28.8	10	82.4	436
GRAND TOTALS:				79.2	352.0	158.4	316.8	110	906.4	4792

NOTE:
* AN ADDITIONAL 10% OF THE ESTIMATED PATCHING QUANTITIES WAS ADDED TO BE USED AT THE DISCRETION OF THE ENGINEER.

PATCHING SCHEDULE
FAI 55 (I-55)
D6 PATCHING 2008-1
LOGAN COUNTY