

PATCHING SCHEDULE

APPROX. STA	LOCATION	LENGTH (FT)	WIDTH (FT)	CL A PATCHES TY II, 8" (SQ YD)	CL A PATCHES TY III, 8" (SQ YD)	CL A PATCHES TY IV, 8" (SQ YD)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)@6.67	SAW CUTS (FT)
111+00	NBDL	5	12	6.67				6.67	58
113+30	NBDL	5	12	6.67				6.67	58
130+10	NBDL	5	12	6.67				6.67	58
146+50	NBDL	5	12	6.67				6.67	58
147+00	NBDL	5	12	6.67				6.67	58
147+50	NBDL	5	12	6.67				6.67	58
147+75	NBDL	5	12	6.67				6.67	58
147+85	NBDL	5	12	6.67				6.67	58
148+10	NBDL	6	12	8.00				8.00	60
148+40	NBDL	5	12	6.67				6.67	58
148+50	NBDL	5	12	6.67				6.67	58
149+00	NBDL	30	12			40.00	15	40.00	108
149+50	NBDL	15	12		20.00			20.00	78
150+00	NBDL	34	12			45.33	17	45.33	116
150+80	NBDL	5	12	6.67				6.67	58
151+20	NBDL	12	12		16.00			16.00	72
153+70	NBDL	8	12	10.67				10.67	64
154+10	NBDL	8	12	10.67				10.67	64
154+80	NBDL	8	12	10.67				10.67	64
159+00	NBDL	6	12	8.00				8.00	60
159+80	NBDL	5	12	6.67				6.67	58
161+80	NBDL	5	12	6.67				6.67	58
163+30	NBDL	5	12	6.67				6.67	58
163+70	NBDL	5	12	6.67				6.67	58
166+40	NBDL	6	12	8.00				8.00	60
166+80	NBDL	5	12	6.67				6.67	58
167+30	NBDL	8	12	10.67				10.67	64
171+00	NBDL	7	12	9.33				9.33	62
178+50	NBDL	5	12	6.67				6.67	58
178+90	NBDL	10	12	13.33				13.33	68
183+00	NBDL	6	12	8.00				8.00	60
186+30	NBDL	5	12	6.67				6.67	58
187+00	NBDL	5	12	6.67				6.67	58
STA. EQU.									
132+55	NBDL	10	12	13.33				13.33	68
133+00	NBDL	6	12	8.00				8.00	60
133+80	NBDL	6	12	8.00				8.00	60
134+20	NBDL	6	12	8.00				8.00	60
175+80	NBDL	20	12			26.67	10	26.67	88
176+50	NBDL	5	12	6.67				6.67	58
184+20	NBDL	8	12	10.67				10.67	64
189+10	NBDL	5	12	6.67				6.67	58
189+90	NBDL	5	12	6.67				6.67	58
190+05	NBDL	5	12	6.67				6.67	58
190+20	NBDL	14	12		18.67			18.67	76
191+20	NBDL	6	12	8.00				8.00	60
192+60	NBDL	6	12	8.00				8.00	60
193+00	NBDL	25	12			33.33	13	33.33	98
193+90	NBDL	5	12	6.67				6.67	58
194+50	NBDL	15	12		20.00			20.00	78
195+80	NBDL	10	12	13.33				13.33	68
196+70	NBDL	6	12	8.00				8.00	60
197+00	NBDL	8	12	10.67				10.67	64
197+10	NBDL	5	12	6.67				6.67	58
STA. EQU.									
33+00	NBDL	5	12	6.67				6.67	58
33+30	NBDL	5	12	6.67				6.67	58
36+00	NBDL	6	12	8.00				8.00	60
TOTAL: NORTHBOUND LANES				425.33	109.33	145.33	55	680.00	4,092
TOTAL: SOUTHBOUND LANES				357.33	116.00	157.33	59	630.67	3,538
TOTAL: SOUTHBOUND AND SOUTHBOUND LANES				782.67	225.33	302.67	114	1,310.67	7,630
+ 10% *				78.33	25.67	30.33	11	131.33	76
GRAND TOTALS:				861.00	251.00	330.00	125	1,442.00	7,706

NOTE:

\* AN ADDITIONAL 10% OF THE ESTIMATED PATCHING QUANTITIES WAS ADDED TO BE BE USED AT THE DISCRETION OF THE ENGINEER.

PATCHING SCHEDULE  
FAI 172 (I-172)  
SECTION D6 PATCHING 2009  
ADAMS COUNTY