

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	•	MACOUPIN	18	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• D6 INTERMITTENT RS 2009

PAVING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	HMA SURF REM 1.75" (SQ YD)	BIT MATL PR CT (TON)	SURFACE DEPTH (INCHES)	POLYMER SURFACE N105 (TON)
<b>I-55 MAINLINE</b>					
<b>NORTHBOUND</b>					
STA 300+00.00 TO STA 325+50.00	12	3,400.00	1.29	1.75	333.20
STA 394+00.00 TO STA 459+00.00	12	8,666.67	3.29	1.75	849.33
STA 614+50.00 TO STA 623+00.00	12	1,133.33	0.43	1.75	111.07
STA 628+00.00 TO STA 635+00.00	12	933.33	0.35	1.75	91.47
STA 645+00.00 TO STA 664+00.00	12	2,533.33	0.96	1.75	248.27
STA 675+32.00 TO STA 676+32.00	24	266.67	0.10	1.75	26.13
STA 677+48.00 TO STA 678+48.00	24	266.67	0.10	1.75	26.13
STA 678+48.00 TO STA 689+00.00	12	1,402.67	0.53	1.75	137.46
STA 796+00.00 TO STA 806+00.00	12	1,333.33	0.51	1.75	130.67
STA 173+50.00 TO STA 245+50.00	12	9,600.00	3.65	1.75	940.80
<b>SOUTHBOUND</b>					
STA 425+00.00 TO STA 474+00.00	12	6,533.33	2.48	1.75	640.27
STA 497+00.00 TO STA 528+00.00	12	4,133.33	1.57	1.75	405.07
STA 675+04.00 TO STA 676+04.00	24	266.67	0.10	1.75	26.13
STA 677+36.00 TO STA 678+36.00	24	266.67	0.10	1.75	26.13
<b>TOTAL</b>		<b>40,736.00</b>	<b>15.46</b>		<b>3,992.13</b>

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FOOT)	URETHANE PAVT MARK LINE - 5" EDGE LINE (FOOT)	PAVT MARK CENTER LINE (FOOT)	SHORT TERM PAVT MK (FOOT)	WORK ZONE PAVT MARK REM (SQ FT)	RAISED REFL (EACH)	RAISED REFL (EACH)
<b>I-55 MAINLINE</b>							
<b>NORTHBOUND</b>							
STA 300+00.00 TO STA 325+50.00	2,550.00	2,550.00	640.00	357.00	119.00	32	32
STA 394+00.00 TO STA 459+00.00	6,500.00	6,500.00	1,630.00	910.00	303.33	81	81
STA 614+50.00 TO STA 623+00.00	850.00	850.00		34.00	11.33		
STA 628+00.00 TO STA 635+00.00	700.00	700.00		28.00	9.33		
STA 645+00.00 TO STA 664+00.00	1,900.00	1,900.00		76.00	25.33		
STA 675+32.00 TO STA 676+32.00	100.00	100.00	30.00	14.00	4.67	1	1
STA 677+48.00 TO STA 678+48.00	100.00	100.00	30.00	14.00	4.67	1	1
STA 678+48.00 TO STA 689+00.00	1,052.00	2,104.00		42.08	14.03		
STA 796+00.00 TO STA 806+00.00	1,000.00	2,000.00		40.00	13.33		
STA 173+50.00 TO STA 245+50.00	7,200.00	7,200.00		288.00	96.00		
<b>SOUTHBOUND</b>							
STA 425+00.00 TO STA 474+00.00	4,900.00	4,900.00	1,230.00	686.00	228.67	61	61
STA 497+00.00 TO STA 500+00.00	300.00	300.00	80.00	42.00	14.00	4	4
STA 500+00.00 TO STA 528+00.00	2,800.00	2,800.00		112.00	37.33		
STA 675+04.00 TO STA 676+04.00	100.00	100.00	30.00	14.00	4.67	1	1
STA 677+36.00 TO STA 678+36.00	100.00	100.00	30.00	14.00	4.67	1	1
<b>TOTAL</b>		<b>32,204.00</b>	<b>3,700.00</b>	<b>2,671.08</b>	<b>890.36</b>	<b>182</b>	<b>182</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAI 55  
 SECTION D6 INTERMITTENT RS 2009  
 MACOUPIN COUNTY

SCALE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_