

INDEX OF SHEETS

- 1 COVER SHEER
- 2 SIGNATURES /GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 MATERIAL SCHEDULES
- 5-6 APPROACH DETAILS
- 7 BEARING DETAILS

STANDARDS

701001-01

GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

THE ORGANIC ZINC RICH PRIMER/EPOXY/URETHANE PAINT SYSTEM SHALL BE USED FOR PAINTING OF NEW STRUCTURAL STEEL EXCEPT WHERE OTHERWISE NOTED. THE ENTIRE SYSTEM SHALL BE SHOP APPLIED, WITH THE EXCEPTION THAT MASKED OFF CONNECTION SURFACES, FIELD INSTALLED FASTENERS AND DAMAGED AREAS SHALL BE TOUCHED UP IN THE FIELD. THE COLOR OF THE FINAL FINISH COAT SHAL BE REDDISH BROWN, MUNSELL NO 2.5YR 3/4.

LOAD CARRYING COMPONENTS DESIGNATED "NTR" SHALL CONFORM TO THE SUPPLEMENTAL REQUIREMENTS FOR NOTCH TOUGHNESS, ZONE 2.

COST OF REMOVAL AND RE-INSTALLATION OF ALL STEEL MEMBERS NECESSARY TO COMPLETE THE WORK AS DETAILED ON THE PLANS AND AS SPECIFIED IN THE SPECIAL PROVISIONS SHALL BE INCLUDED WITH FURNISHING AND ERECTING STRUCTURAL STEEL.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	April 8 20 08 <i>[Signature]</i> ENGINEER OF OPERATIONS
EXAMINED	April 9 20 08 <i>[Signature]</i> ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED	April 9 20 08 <i>[Signature]</i> ENGINEER OF PROGRAM DEVELOPMENT

GENERAL NOTES / SIGNATURES
SUGAR CREEK COVERED BRIDGE
D6 COV BR PLANK REM & REPL
SANGAMON COUNTY