

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES					
				FAI 72 ROADWAY 4 LANE 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0093 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0094 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0095 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0096 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0097 90% FED 10% STATE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	X031-2A	X031-2A	X531-2A	X531-2A	X231-2A
20200100	EARTH EXCAVATION	CU YD	1232	1232					
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.81	0.81					
25100115	MULCH, METHOD 2	ACRE	0.81	0.81					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	81	81					
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	4013	4013					
35650500	BASE COURSE WIDENING 10"	SQ YD	174	174					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19053	19053					
40600300	AGGREGATE (PRIME COAT)	TON	380	380					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	44	44					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	71	71					
40600990	TEMPORARY RAMP	SQ YD	1733	1733					
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N105	TON	13890	13890					
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	9541	9541					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	203	203					
44213100	PAVEMENT FABRIC	SQ YD	18	18					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	129	129					
44000100	PAVEMENT REMOVAL	SQ YD	163	163					
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	55146	55146					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	960	960					
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	115402	115402					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	17883	17883					
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	7400		1740	1749	1506	1506	899
44004250	PAVED SHOULDER REMOVAL	SQ YD	3333	3333					
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	429	429					
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	558	558					
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	107	107					
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	137	137					
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	2240	2240					
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	41	41					
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	18	18					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	85	85					
44213000	PATCHING REINFORCEMENT	SQ YD	3471	3471					
44213200	SAW CUTS	FOOT	10466	10466					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1352	1352					
48203043	HOT-MIX ASPHALT SHOULDERS, 11 1/2"	SQ YD	3406	3406					
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5992	5992					
50102400	CONCRETE REMOVAL	CU YD	137.7		11.6	11.6	49.2	53.3	12
50157300	PROTECTIVE SHIELD	SQ YD	3284				1124	1124	1036
50300100	FLOOR DRAINS	EACH	156		30	30	40	40	16
50300255	CONCRETE SUPERSTRUCTURE	CU YD	155.9		13.8	14.1	55.3	59.4	13.3
50300260	BRIDGE DECK GROOVING	SQ YD	7400		1740	1749	1506	1506	899
50300300	PROTECTIVE COAT	SQ YD	7603	203	1740	1749	1506	1506	899
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	10030		2355	2355	1710	1710	1900
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	56		12	12	12	12	8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24110		3490	3530	7040	7040	3010
50800515	BAR SPLICERS	EACH	224		28	28	72	72	24
51500200	RELOCATING NAME PLATES	EACH	2				1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	658		96	96	192	192	82

FILE NAME = c:\projects\74171\d\shstsq.74171.dgn	USER NAME = swartzu	DESIGNED - JLD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (1 OF 2)			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - RWS	REVISED -		SCALE: NA	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	72	(58,74)(66,67)RS-1	MACON	88	4
		CHECKED - WES	REVISED -					CONTRACT NO. 74171					
		DATE - 10-07	REVISED -					ILLINOIS FED. AID PROJECT					