

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS INDICATED ON THE CHECKSHEET; AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED NEAR MAROA ON US-51 MACON COUNTY. THE PROJECT INCLUDES THE STRUCTURE NUMBERS 058-0117 and 058-0118.

THE WORK INCLUDED IN THIS PROJECT CONSISTS OF CONSTRUCTION OF PCC BASE COURSE WIDENING, REMOVAL OF THE EXISTING NEOPRENE JOINT SEAL EXPANSION JOINTS AND REPLACING THEM WITH PREFORMED JOINT STRIP SEAL EXPANSION JOINTS, AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR WORK.

THE TOTAL QUANTITY OF POLYUREA PAVEMENT MARKING TYPE I - LINE 4 INCH CONSISTS OF:

STR#	YELLOW FT	WHITE FT
058-0117	361	361
058-0118	361	361

THE TOTAL QUANTITY OF POLYUREA PAVEMENT MARKING TYPE I - LINE 6 INCH CONSISTS OF:

STR#	WHITE FT
058-0117	90
058-0118	90

THE REFLECTIVE LENSE OF ALL RAISED REFLECTIVE MARKERS LOCATED BETWEEN THE START OF TAPER AND THE ABUTMENT OF THE FIRST STRUCTURE SHALL BE REMOVED PRIOR TO STAGE I CONSTRUCTION. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL. REPLACEMENT OF THE DIRECTIONAL WHITE REFLECTORS AT THE COMPLETION OF STAGE II WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR REPLACEMENT REFLECTOR.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATION AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF 96 HOURS ADVANCE NOTICE IS REQUESTED.

INDEX OF SHEETS

SHEET NO

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5 STAGE CONSTRUCTION I
- 6 STAGE CONSTRUCTION II
- 7-12 BRIDGE PLAN AND DETAILS 058-0117 & 0118
- 13 PREFORMED JOINT STRIP SEAL
- 14 BAR SPLICER ASSEMBLY

LIST OF HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-01 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701006-02 OFF-ROAD OPERATIONS, 2L 2W, 15' TO 24" AWAY, SPEEDS > 45 MPH
- 701011-01 OFF-ROAD MOVING OPERATIONS, 2L 2W, DAY ONLY, FOR SPEEDS > 45 MPH
- 701400-02 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701402-06 LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
- 701901 TRAFFIC CONTROL DEVICES
- 704001-04 TEMPORARY CONCRETE BARRIER
- 720001 SIGN PANEL MOUNTING DETAILS
- 720006-01 SIGN PANEL ERECTION DETAILS
- 780001-01 TYPICAL PAVEMENT MARKINGS
- 781001-02 TYPICAL APPLICATIONS OF RAISED REFLECTIVE PAVEMENT MARKERS