

Bridge Repair Schedule						
Structure Number	Length	Concrete Removal	Concrete Superstructure	Reinforcement Bars, Epoxy Coated	Bar Splicers	Preformed Joint Strip Seal
		CU YD	CU YD	POUND	EACH	FOOT
058-0117						
Stage I	91.17	9.6	9.6	1700		24.8
Stage II		8.1	8.1	1360		20.2
TOTAL	91.17	17.7	17.7	3030	31	45.0
058-0118						
Stage I	91.17	8.1	8.1	1575		24.8
Stage II		6.8	6.8	1305		20.2
TOTAL	91.17	14.9	14.9	2880	29	45.0
GRAND TOTAL	182.34	32.6	32.6	5910	60	90

Pavement Marking Schedule					
STRUCTURE NUMBER	Paint Pavement Marking Removal	Short Term Pavement Marking	Work Zone Pavement Marking Removal	Polyurea Pavement Marking Type I - Line 4"	Polyurea Pavement Marking Type I - Line 6"
	SQ FT	FEET	SQ FT	FEET	FEET
058-0117					
STAGE I	160		721.4		
STAGE II	119	33	721.4	722	90
Total	279	33	1443	722	90
058-0118					
STAGE I	160		721.4		
STAGE II	119	33	721.4	722	90
Total	279	33	1443	722	90
GRAND TOTAL	558	66	2886	1444	180