

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS INDICATED ON THE CHECKSHEET; AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED EAST OF EFFINGHAM ON I-70 IN EFFINGHAM COUNTY. THE PROJECT INCLUDES THE STRUCTURE NUMBER 025-0062 AN OVERHEAD STRUCTURE CARRYING TR258 (1650E) OVER I-70.

THE WORK INCLUDED IN THIS PROJECT CONSISTS OF REMOVAL AND REPLACEMENT OF FOUR BEAMS AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

THE EFFINGHAM COUNTY ENGINEER SHALL BE CONTACTED ONE WEEK PRIOR TO CLOSURE OF THE TOWNSHIP ROAD. GREG KOESTER AT (217)342-6550

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATION AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF 96 HOURS ADVANCE NOTICE IS REQUESTED.

INDEX OF SHEETS

SHEET NO

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
- \* 3 SUMMARY OF QUANTITIES
- 4-9 BRIDGE REPAIR PLANS
- \*3A. STANDARD DETAIL

LIST OF HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-01 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701101-01 OFF-ROAD OPERATIONS, MULTI-LANE, 15' to 24" FROM EDGE OF PAVEMENT
- 701106-01 OFF-ROAD OPERATIONS, MULTI-LANE, MORE THAN 15' AWAY
- 701400-02 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-04 LANE CLOSURE, FREEWAY/EXPRESSWAY, DAYTIME ONLY
- 701901 TRAFFIC CONTROL DEVICES
- 704001-04 TEMPORARY CONCRETE BARRIER
- BLR21-7 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

FILE NAME = c:\projects\74311d\shcover_74311.dgn	USER NAME = teasleyck	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES &amp; INDEX OF SHEETS</b>	F.A.I. RTE. 70	SECTION .	COUNTY EFFINGHAM	TOTAL SHEETS 9	SHEET NO. 2	<i>Rev.</i>
PLOT SCALE = 20,0000' / 1" IN.	CHECKED -	REVISED -	CONTRACT NO. 74311								
PLOT DATE = 3/27/2008	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
SCALE: SHEET NO. OF SHEETS STA. TO STA.						* 07 MCHD BRIDGE REPAIRS 2009-1					