

REVISED RESURFACING SCHEDULE									
Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
IL 203 RAMPS									
RAMP B1									
+24	TO	+60	75	36	300	0.1	0.5	42	42
+60	TO	1+30	23	70	179	0.1	0.3	25	25
1+30	TO	12+35	16	1105	1964	0.6	2.9	275	275
12+35	TO	16+00	10	365	406	0.1	0.6	57	57
RAMP B2									
-+35	TO	+	9	35	35	0.0	0.1	5	5
+	TO	1+65	13	165	238	0.1	0.4	33	33
1+65	TO	8+46	16	681	1211	0.4	1.8	169	169
8+46	TO	9+10	30	64	213	0.1	0.3	30	30
9+10	TO	9+34	59	24	157	0.0	0.2	22	22
RAMP B3									
+27	TO	+45	65	18	130	0.0	0.2	18	18
+45	TO	+75	35	30	117	0.0	0.2	16	16
+75	TO	1+15	21	40	93	0.0	0.1	13	13
1+15	TO	7+73	16	658	1170	0.4	1.8	164	164
7+73	TO	9+00	15	127	212	0.1	0.3	30	30
9+00	TO	10+10	9	110	110	0.0	0.2	15	15
RAMP B4									
+	TO	2+50	15	250	417	0.1	0.6	58	58
2+50	TO	10+90	16	840	1493	0.5	2.2	209	209
10+90	TO	11+25	21	35	82	0.0	0.1	11	11
11+25	TO	11+50	35	25	97	0.0	0.1	14	14
11+50	TO	11+70	56	20	124	0.0	0.2	17	17
RAMP B5									
+	TO	1+95	10	195	217	0.1	0.3	30	30
1+95	TO	9+00	16	705	1253	0.4	1.9	175	175
9+00	TO	10+19	30	119	397	0.1	0.6	56	56
10+19	TO	10+93	21	74	173	0.1	0.3	24	24
10+93	TO	11+61	28	68	212	0.1	0.3	30	30
RAMP B5 SPUR									
1+35	TO	3+02	18	167	334	0.1	0.5	47	47
RAMP B6									
+40	TO	+80	43	40	191	0.1	0.3	27	27
+80	TO	1+28	28	48	149	0.0	0.2	21	21
1+28	TO	8+87	16	759	1349	0.4	2.0	189	189
8+87	TO	11+00	15	213	355	0.1	0.5	50	50
11+00	TO	12+99	9	199	199	0.1	0.3	28	28
RAMP B7									
-1+35	TO	+	9	135	135	0.0	0.2	19	19
+	TO	1+92	15	192	320	0.1	0.5	45	45
1+92	TO	9+68	16	776	1380	0.4	2.1	193	193
9+68	TO	10+30	23	62	158	0.0	0.2	22	22
10+30	TO	10+65	45	35	175	0.1	0.3	25	25
RAMP B8									
+35	TO	+65	62	30	207	0.1	0.3	29	29
+65	TO	1+44	31	79	272	0.1	0.4	38	38
1+44	TO	12+05	16	1061	1886	0.6	2.8	264	264
12+05	TO	14+10	10	205	228	0.1	0.3	32	32
SUB-TOTAL				9860	18338	5.7	27.5	2567	2567

REVISED RESURFACING SCHEDULE									
Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
IL 111 RAMPS									
RAMP C1									
+	TO	1+49	4	149	66	0.0	0.1	9	9
1+49	TO	2+26	13	77	111	0.0	0.2	16	16
2+26	TO	2+92	24	66	176	0.1	0.3	25	25
2+92	TO	17+50	16	1458	2592	0.8	3.9	363	363
17+50	TO	22+71	16	521	926	0.3	1.4	130	130
22+71	TO	23+43	11	72	88	0.0	0.1	12	12
23+43	TO	25+00	5	157	87	0.0	0.1	12	12
RAMP C2									
-1+00	TO	+	14	100	156	0.0	0.2	22	22
+	TO	+98	16	98	174	0.1	0.3	24	24
+98	TO	2+08	25	110	306	0.1	0.5	43	43
2+08	TO	13+65	16	1157	2057	0.6	3.1	288	288
13+65	TO	15+45	16	180	320	0.1	0.5	45	45
RAMP C3									
-1+85	TO	+57	18	242	484	0.2	0.7	68	68
+57	TO	1+10	24	53	141	0.0	0.2	20	20
1+10	TO	10+78	16	968	1721	0.5	2.6	241	241
10+78	TO	11+10	18	32	64	0.0	0.1	9	9
RAMP C4									
+	TO	4+35	8	435	387	0.1	0.6	54	54
4+35	TO	5+75	23	140	358	0.1	0.5	50	50
5+75	TO	20+45	16	1470	2613	0.8	3.9	366	366
20+45	TO	26+50	10	605	672	0.2	1.0	94	94
RAMP C5									
+	TO	2+00	12	200	267	0.1	0.4	37	37
2+00	TO	5+16	16	316	562	0.2	0.8	79	79
5+16	TO	5+80	25	64	178	0.1	0.3	25	25
5+80	TO	16+94	16	1114	1980	0.6	3.0	277	277
RAMP C6									
-2+20	TO	+50	16	270	480	0.2	0.7	67	67
+50	TO	1+65	24	115	307	0.1	0.5	43	43
1+65	TO	10+25	16	860	1529	0.5	2.3	214	214
10+25	TO	11+77	26	152	439	0.1	0.7	61	61
RAMP C7									
-+95	TO	+69	14	164	255	0.1	0.4	36	36
+69	TO	1+93	25	124	344	0.1	0.5	48	48
1+93	TO	14+50	16	1257	2235	0.7	3.4	313	313
14+50	TO	16+20	27	170	510	0.2	0.8	71	71
16+20	TO	17+30	16	110	196	0.1	0.3	27	27
RAMP C8									
+	TO	3+65	6	365	243	0.1	0.4	34	34
3+65	TO	5+71	21	206	481	0.2	0.7	67	67
5+71	TO	23+15	16	1744	3100	1.0	4.7	434	434
SUB-TOTAL				15321	26605	8.3	39.9	3725	3725

FILE NAME = c:\projects\ad06207\plan\p1n06207a.dgn	USER NAME = alfordb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/24/2008	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 270	SECTION 60-(1,2,3,4)RS-2	COUNTY MADISON	TOTAL SHEETS 193	SHEET NO. 22
CONTRACT NO. 76A90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				