

REVISED RESURFACING SCHEDULE									
Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
IL 255 RAMPS									
RAMP D2									
209+57	TO	212+00	12	243	324	0.1	0.5	45	45
212+00	TO	213+07	14	107	166	0.1	0.2	23	23
213+07	TO	214+07	16	100	178	0.1	0.3	25	25
214+07	TO	230+35	16	1628	2894	0.9	4.3	405	405
230+35	TO	231+30	17	95	179	0.1	0.3	25	25
231+30	TO	235+20	14	390	607	0.2	0.9	85	85
RAMP D4									
477+07	TO	483+61	16	654	1163	0.4	1.7	163	163
483+61	TO	485+86	15	225	375	0.1	0.6	53	53
RAMP D5									
578+37	TO	581+75	10	338	376	0.1	0.6	53	53
581+75	TO	617+82	16	3607	6412	2.0	9.6	898	898
617+82	TO	625+45	8	763	678	0.2	1.0	95	95
RAMP D8									
867+80	TO	871+23	14	343	534	0.2	0.8	75	75
871+23	TO	872+65	22	142	347	0.1	0.5	49	49
872+65	TO	888+24	16	1559	2772	0.9	4.2	388	388
SUB-TOTAL				10194	17005	5.3	25.5	2381	2381

REVISED RESURFACING SCHEDULE									
Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
MAINLINE				82571	207989	65.1	312.0	29119	29119
IL 3 RAMPS				17330	29990	9.4	45.0	4199	4199
IL 203 RAMPS				9860	18338	5.7	27.5	2567	2567
IL 111 RAMPS				15321	26605	8.3	39.9	3725	3725
IL 255 RAMPS				10194	17005	5.3	25.5	2381	2381
GRAND TOTALS				135276	299927	93.8	449.9	41990	41990

FILE NAME =
c:\projects\ed06207\plan\pin06207a.dgn

USER NAME = oifordb
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 4/25/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-11,2,3,4RS-2	MADISON	193	23
CONTRACT NO. 76A90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				