

| *ACCELERATION/DECELERATION LANES IL RTE. 3 AND IL RTE. 203 RESURFACING SCHEDULE | | | | | | | | | |
|---|----|----------|-----|--------|--|----------------------------------|------------------------|----------------------------|--------------------------|
| LOCATION | | | L/R | (FOOT) | 44000159 | 40600200 | 40600300 | X4066580 | X0322729 |
| | | | | | HOT MIX ASPHALT SURFACE REMOVAL 2 1/2" | BITUMINOUS MATERIAL (PRIME COAT) | AGGREGATE (PRIME COAT) | POLY HMA SC SMA N80 2 1/2" | MATERIAL TRANSFER DEVICE |
| STA | TO | STA | | | (SQ YD) | (TON) | (TON) | (TON) | (TON) |
| IL RTE. 3 | | | | | | | | | |
| ACC/DEC LANE @ RAMP A2 TO A3 | | | | | | | | | |
| 1358+70. | TO | 1361+90. | RT | 320 | 640.0 | 0.20 | 0.96 | 44.8 | 44.8 |
| ACC/DEC LANE @ RAMP A6 TO A7 | | | | | | | | | |
| 1356+50. | TO | 1364+00. | LT | 750 | 1500.0 | 0.47 | 2.25 | 105.0 | 105.0 |
| IL RTE. 111 | | | | | | | | | |
| ACC/DECLANE @ RAMP C2 TO C3 | | | | | | | | | |
| 192+00. | TO | 196+50. | LT | 450 | 900.0 | 0.28 | 1.35 | 63.0 | 63.0 |
| ACC/DEC LANE @ RAMP C6 TO C7 | | | | | | | | | |
| 191+90. | TO | 197+30. | RT | 540 | 1080.0 | 0.34 | 1.62 | 75.6 | 75.6 |
| TOTALS: | | | | | 4120 | 1 | 6 | 288 | 288 |

* NOTE: THE QUANTITIES ABOVE ARE FOR THE ACCELERATION AND DECELERATION LANES BELOW I-270 BRIDGES ON IL RTE 3 AND IL RTE 111. THE STATIONING PROVIDED IS BASED ON CENTERLINE FOR THE ABOVE ROUTES AND SHOULD TIE INTO THE BEGINNING AND ENDING STATIONS ON THE RAMPS PROVIDED ABOVE. SEE DETAIL A1-A1.

