

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31.8	31.8		
40600300	AGGREGATE (PRIME COAT)	TON	152.3	152.3		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	300	300		
40600990	TEMPORARY RAMP	SQ YD	103	103		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	6396	6396		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4264	4264		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6540	6540		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1582	1582		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2497	2497		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	-----	-----
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6656	6656		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48641	48641		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	467	467		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1109	1109		
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	94	94		
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	48641	48641		
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	467	467		
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	41	41		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	312	312		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	312	312		

* SPECIALTY ITEMS