

PAVEMENT MARKING SCHEDULE														
LOCATION		PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID									RAISED REFLECTIVE PAVEMENT MARKERS			
		12" YELLOW SOLID DIAGONAL	24" WHITE SOLID STOP BAR	4" YELLOW SKIP-DASH, 10' - 30'	4" SOLID YELLOW CENTERLINE	4" SOLID DOUBLE YELLOW MEDIAN	4" YELLOW SKIP-DASH, 2' - 6'	4" SOLID WHITE EDGE LINE	4" SOLID WHITE LANE LINE	LETTERS & SYMBOLS, LEFT TURN ARROWS	REMOVAL	TWO-WAY AMBER	ONE-WAY AMBER CRYSTAL	
STA	STA	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ FOOT	EACH	EACH	EACH	EACH
US 50														
3341+06	TO 3342+56			40	150						2	2		
3342+56	TO 3346+56	108				1600		800			20		20	
3346+56	TO 3349+26	95				1080	68	540			14		14	
3349+26	TO 3351+62	38				944		472	236	47	22		16	6
3351+62	TO 3352+31													
3352+31	TO 3354+66	37				940		470	235	47	22		16	6
3354+66	TO 3357+36	89				1080	68	540			14		14	
3357+36	TO 3361+36	100				1600		800			20		20	
3361+36	TO 3365+36			100	400			800			5	5		
3365+36	TO 3515+45			3760				30018			188	188		
3515+45	TO 3519+45				800			800			5	5		
TR 104														
STA 19+93			21											
STA 20+95			21											
SUB-TOTALS		467	41	3900	1350	7244	136	35540	471	94	312	200	100	12
TOTALS		467	41			48641				94	312		312	

WORK ZONE PAVEMENT MARKING SCHEDULE							
LOCATION		SHORT-TERM PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL	
		SHOULDER MARKING	CENTERLINE	MEDIAN	LANE LINE		
STA	STA	FEET	FEET	FEET	FEET	SQ FT	
3341+06	TO 3342+56	16	16			11	
3342+56	TO 3346+56	32		80		37	
3346+56	TO 3349+26	24		56		27	
3349+26	TO 3351+62	24		48	24	32	
3351+62	TO 3352+31						
3352+31	TO 3354+66	24		48	24	32	
3354+66	TO 3357+36	24		56		27	
3357+36	TO 3361+36	32		80		37	
3361+36	TO 3365+36	32	40			24	
3365+36	TO 3515+45	1208	1368			859	
3515+45	TO 3519+45	32	40			24	
SUB-TOTALS		1448	1464	368	48	1109	
2 APPLICATIONS		2896	2928	736	96	-	
TOTALS			6656			1109	

PAVING SCHEDULE									
LOCATION		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N90, 2.25"	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90, 1.5"	HOT-MIX ASPHALT SHOULDERS, 3.75"	AGGREGATE WEDGE SHOULDER, TYPE B	STRIP REFLECTIVE CRACK CONTROL TREATMENT	
STA	STA	TON	TON	TON	TON	TON	TON	TON	FOOT
3341+06	TO 3342+56	0.28	1.35	56.7	37.8	21.0	13.3		450
3342+56	TO 3346+56	0.93	4.47	187.6	125.1	56.0	35.5		1200
3346+56	TO 3349+26	0.78	3.74	156.9	104.6	37.8	23.9		810
3349+26	TO 3354+66	1.65	7.92	332.6	221.8	75.6	47.9		1620
3354+66	TO 3357+36	0.78	3.74	156.9	104.6	37.8	23.9		810
3357+36	TO 3361+36	0.93	4.47	187.6	125.1	56.0	35.5		1200
3361+36	TO 3362+86	0.28	1.35	56.7	37.8	21.0	13.3		450
3362+86	TO 3519+45	26.13	125.27	5261.4	3507.6	2192.3	1388.4		0
TOTALS		31.8	152.3	6396	4264	2497	1582		6540