

# ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL	ACHSIP	ACM	ACHSIP	ACHSIP				
				1000-1A	1000-1A	Y031-1F	Y031-1F				
				ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS				
				RT TURN LANE		I-255	EASTPORT				
				HSIP	STP	RAMPS 3 & 4	PLAZA DR.				
				90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	FOURNIE LN.				
							57 Collinsville 90% FEDERAL 5% STATE				
20200100	EARTH EXCAVATION	CU YD	1190	1052	138						
20400800	FURNISHED EXCAVATION	CU YD	588	588							
20800150	TRENCH BACKFILL	CU YD	105	105							
25000210	SEEDING, CLASS 2A	ACRE	1.2	0.6	0.6						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108	54	54						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108	54	54						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108	54	54						
25100115	MULCH, METHOD 2	ACRE	1.2	0.6	0.6						
25100630	EROSION CONTROL BLANKET	SQ YD	1566	1566							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120	60	60						
28000300	TEMPORARY DITCH CHECKS	EACH	5	5							
28000400	PERIMETER EROSION BARRIER	FOOT	3710	3710							
28000500	INLET AND PIPE PROTECTION	EACH	22	22							
28100103	STONE RIPRAP, CLASS A2	SQ YD	40	40							
28200200	FILTER FABRIC	SQ YD	40	40							
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5131	4446	685						
30201500	LIME	TON	99	86	13						
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	3923	3238	685						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.3	3.1	0.2						
40600300	AGGREGATE (PRIME COAT)	TON	16	15	1						
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1324	1209	115						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	196	196							
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	53	53							
40600990	TEMPORARY RAMP	SQ YD	249	246							
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	876	818	58						
44000100	PAVEMENT REMOVAL	SQ YD	393	393							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	61	61							
44003100	MEDIAN REMOVAL	SQ FT	5840	5840							
44004250	PAVED SHOULDER REMOVAL	SQ YD	3459	3459							
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	22	22							
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	33	33							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	160	160							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2236	2236							
50105220	PIPE CULVERT REMOVAL	FOOT	87	87							

FILE NAME =  
 USER NAME = conoverpj  
 DESIGNED -  
 DRAWN -  
 PLOT SCALE = 50.0000' / IN.  
 PLOT DATE = 3/18/2008

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 1 OF 5 SHEETS STA. TO STA.

Rev. 5-27-08

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9111	73-151S	MADISON	64	3
CONTRACT NO. 76B22				

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT