

**PAVEMENT MARKING SCHEDULE**

STATION	STATION	DESCRIPTION	SHORT-TERM PAVT MKING (FOOT)	TEMP PVT MK LN 4" (FOOT)	TEMP PVT MK LN 8" (FOOT)	TEMP PVT MK LN 12" (FOOT)	TEMP PVT MK LN 24" (FOOT)	TEMP PAVT MK L&S L&S (SQ FT)	WORK ZONE PAVT MK REM (SQ FT)	THPL PVT MK LTR & SYM (SQ FT)	THPL PVT MK LN 4" (FOOT)	THPL PVT MK LN 8" (FOOT)	THPL PVT MK LN 12" (FOOT)	THPL PVT MK LN 24" (FOOT)	RAISED REFL PAVT MKR (NOTE 2) (EACH)	PRISMATIC CURB REFL (EACH)	PT PVT MK-RAISED MED (SQ FT)	PAINT PVT MARK CURB (FOOT)
<b>RAMP 4</b>																		
LT 0+40	LT 0+45	Med Ramp Nose															27	
LT 0+43	LT 0+78	CC&G																35
LT 0+40	LT 1+78	LT EOP		144										144				
RT 0+48	RT 1+78	RT EOP		162										162				
RT 0+51	RT 0+60	Stop Bar					18		36					18				
<b>FAU RTE 9111 (HORSESHOE LAKE ROAD)</b>																		
LT 225+48	LT 225+51	Island			114	62			136				114	62				
LT 225+32	LT 225+38	Med Ramp Nose															28	
LT 225+38	LT 225+38	EB Med Curb													3			49
LT 225+38	LT 231+67	WB CC&G		529					208					628		17		
LT 230+55	LT 231+67	WB Med Curb																45
LT 231+67	LT 231+73	Med Ramp Nose															24	
LT 226+12	LT 231+72	WB EOP		560					185					590				
LT 226+82	LT 231+72	WB Ln Line	118	589					184					598				
LT 226+57	LT 226+57	WB Stop Bar					14		28					14				
LT 226+55	LT 226+63	WB Arrows						15.6	16	15.6								
LT 228+85	LT 228+63	WB Arrow						15.6	16	15.6								
LT 226+38	LT 231+67	EB CC&G		629					208					629		32		
LT 226+86	LT 228+26	EB Lt. Turn Ln		82					20					82				
LT 228+26	LT 232+11	EB Lt. Turn Ln	77	385					127					355		11		
LT 228+87	LT 229+05	EB Arrow						15.6	16	15.6								
LT 231+12	LT 231+20	EB Arrow						15.6	16	15.6								
LT 231+15	LT 231+23	WB Arrow						15.6	16	15.6								
RT 231+87	RT 231+87	EB Stop Bar					12		24									
RT 228+07	RT 231+88	EB EOP		656					217					658				
RT 228+86	RT 228+25	EB RL Turn Ln		62					20					62				
RT 228+25	RT 231+98	EB RL Turn Ln	75	378					123					378		10		
RT 232+11	LT 232+11	EB Stop Bar					14		28					14				
RT 228+87	RT 229+05	EB Arrow						15.6	16	15.6								
RT 231+12	RT 231+20	EB Arrows						15.6	16	15.6								
RT 231+98	RT 232+28	Island		108	39				112				108	39				
<b>FOURNIE LANE</b>																		
LT 10+54	LT 10+73	LT EOP		62					17					52				
LT 10+55	LT 10+72	Stop Bar					24		48					24				
RT 10+22	RT 10+73	RT EOP		86					33					86				
<b>EASTPORT PLAZA DRIVE</b>																		
RT 47+83	RT 48+84	RT EOP		110					36					110				
RT 47+90	RT 48+82	Stop Bar					18		36					18				
RT 48+18	RT 48+55	Dbi Ln Line	5	48					16					48		8		
RT 48+50	LT 48+53	Lt Turn Arrow						15.6	16	15.6								
RT 48+84	LT 48+81	Bike Path			243				243					243				
LT 47+93	LT 47+83	Stop Bar					12		24					12				
LT 47+83	LT 48+66	Lane Line	15	73					24					73				
LT 47+82	LT 48+67	LT EOP		168					55					168				
LT 47+83	LT 48+07	Stop Bar					18		36					18				
LT 48+18	LT 48+18	Stop Bar					12		24					12				
RT 48+78	RT 48+84	RT EOP		26					8					26				
RT 48+79	RT 49+04	Dbi Ln Line	3	25					8					25		3		
LT 48+80	LT 48+84	Lane Line	5	24					8					24				
LT 48+81	LT 48+84	LT EOP		24					8					24				
<b>FAU RTE 9111 (HORSESHOE LAKE ROAD)</b>																		
RT 232+84	RT 232+81	Island			88	34			93					88	34			
RT 233+84	RT 242+85	RT EOP		901					297					901				
LT 232+85	LT 242+85	Median	366	3960		255			1582					3960				52
LT 233+84	LT 233+84	Stop Bar					12		24					12				
LT 232+71	LT 232+78	WB Stop Bar					23		46					23				
LT 232+71	LT 235+45	WB Ln Line	56	274					80					274		8		
LT 233+80	LT 233+80	WB Arrows						15.6	16	15.6								
LT 234+80	LT 234+88	WB Arrow						15.6	16	15.6								
LT 235+45	LT 237+25	WB Ln Line		47					16					47				
LT 233+14	LT 242+85	LT EOP		971					320					971				
<b>TOTAL</b>			740	11054	311	633	177	156	6002	156	11054	311	177	103	52	79	132	

PAVEMENT MARKING NOTES:  
 1. RAISED REFLECTIVE PAVEMENT MARKER QUANTITY INCLUDES THE FOLLOWING TYPES:  
 64 EACH EACH ONE-WAY AMBER MARKERS  
 45 EACH EACH ONE-WAY CRYSTAL MARKERS  
 EACH EACH TWO-WAY AMBER MARKERS  
 108 EACH EACH TOTAL

390

TO BE PAID FOR AS PAINT PAVEMENT MARKING - LINE 12" (78001150)

**EROSION CONTROL SCHEDULE**

STATION	STATION	EROSION CONTROL BLANKET (SQ YD)	TEMPEROS CONTR SEED (POUND)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROS BAR (FOOT)	INLET & PIPE PROTECTION (EACH)
<b>RAMP 4</b>						
RT 1+56						1
LT 0+73	LT 1+78				105	
<b>HORSESHOE LAKE ROAD</b>						
LT 226+40						1
LT 226+60				1		
RT 226+50						
LT 228+85						1
LT 226+80						1
LT 227+15						1
LT 227+40						1
LT 227+65						1
LT 227+90						1
LT 228+15						1
LT 228+40						1
LT 228+65						1
LT 228+90						1
LT 229+15						1
LT 229+40						1
LT 229+65						1
LT 229+90						1
LT 230+00						1
LT 230+80						1
LT 231+50				1		
LT 232+82						1
RT 233+02						1
LT 233+50				1		
RT 238+00				1		
RT 239+66						1
LT 239+55						1
RT 1+78 (RAMP 4)	LT 232+17				741	
LT 225+06.5	LT 232+45		90			
RT 225+06.5	RT 232+12	1586				
RT 225+06.5	RT 232+80		20			
RT 225+38	RT 231+87				857	
LT 232+45	LT 242+85		20			
LT 232+71	LT 242+90				1031	
RT 232+80	RT 242+85		20			
RT 233+01	RT 242+90				993	
<b>EASTPORT PLAZA DRIVE</b>						
RT 48+83	RT 48+83					68
LT 48+84	LT 48+87					85
RT 48+81	RT 49+09					28
LT 48+85	LT 49+07					22
<b>TOTALS</b>		1586	120	5	3710	22

**PIPE UNDERDRAIN SCHEDULE**

STATION	STATION	CONC HOWL FOR P DRAIN (EACH)	PIPE UNDERDRAINS 4 (FOOT)	PIPE UNDERDRAINS 4 SP (FOOT)
<b>FAU RTE 9111 (HORSESHOE LAKE ROAD)</b>				
LT 226+14	LT 228+80	1	276	20
LT 228+80	LT 231+70	1	280	20
LT 233+26	LT 236+57	1	336	11
LT 236+80	LT 239+60	1	300	9
LT 239+72	LT 242+85	1	313	8
RT 225+06.5	RT 228+38	1	333	10
RT 228+42	RT 231+64	1	322	14
RT 233+32	RT 235+80	1	333	23
RT 236+84	RT 239+60	1	295	4
RT 239+72	RT 242+85	1	313	4
<b>Ramp 4</b>				
LT 0+82	LT 1+54		62	
LT 1+54	LT 1+78	1	23	10
RT 1+60	RT 1+78	1	18	10
<b>TOTAL</b>			12	3205

NOTES: 1. SEE STD 601001 FOR MORE INFORMATION.