

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN TOTAL	ACHSIP	ACM	ACHSIP	ACHSIP				
	1000-1A	1000-1A	Y031-1F	Y031-1F	TRAFFIC SIGNALS	TRAFFIC SIGNALS		
QUANTITIES	ROADWAY	ROADWAY						
		RT TURN LANE	I-255	PLAZA DR.				
	HSIP	STP	RAMPS 3 & 4	FOURNIE LN.				
	90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	51 Collinsville 90% FEDERAL 5% STATE				

CODE NO	ITEM	UNIT	URBAN TOTAL	ACHSIP 1000-1A	ACM 1000-1A	ACHSIP Y031-1F	ACHSIP Y031-1F				
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1							
54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	5	5							
54205923	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 48"	FOOT	33	33							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2							
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2							
54215163	STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 48"	EACH	2	2							
54248510	CONCRETE COLLAR	CU YD	0.3	0.3							
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	80	80							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	415	415							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	97	97							
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	28	28							
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	12	12							
60107600	PIPE UNDERDRAINS 4"	FOOT	3205	3205							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	144	144							
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EACH	17	17							
60500060	REMOVING INLETS	EACH	3	3							
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 18	FOOT	121	121							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	180	180							
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 12	FOOT	195	195							
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 24	FOOT	164	164							
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1211	1211							
60622800	CONCRETE MEDIAN, TYPE SM-6. 12	SQ FT	3168	3168							
60625900	P. C. C. RAMPED MEDIAN TERMINAL	EACH	3	3							
66500105	WOVEN WIRE FENCE, 4'	FOOT	621		621						
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	650		650						
67100100	MOBILIZATION	L SUM	1	1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1							
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1							
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1							
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1							