

**PAVEMENT MARKING SCHEDULE**

STATION	STATION	DESCRIPTION	SHORT-TERM PAVT MKNG (FOOT)	TEMP PVT MK LN 4" (FOOT)	TEMP PVT MK LN 8" (FOOT)	TEMP PVT MK LN 12" (FOOT)	TEMP PVT MK LN 24" (FOOT)	TEMP PAVT MK L&S (SQ FT)	WORK ZONE PAVT MK REM (SQ FT)	THPL PVT MK LTR & SYM (SQ FT)	THPL PVT MK LN 4" (FOOT)	THPL PVT MK LN 8" (FOOT)	THPL PVT MK LN 12" (FOOT)	THPL PVT MK LN 24 (FOOT)	RAISED REFL PAVT MKR (NOTE 2) (EACH)	PRISMATIC CURB REFL (EACH)	PT PVT MK- RAISED MED (SQ FT)	PAINT PVT MARK CURB (FOOT)
<b>RAMP 4</b>																		
LT 0+40	LT 0+46	Med Ramp Nose															27	35
LT 0+46	LT 0+78	CC&G																
LT 0+40	LT 1+78	LT EOP		144					48				144					
RT 0+49	RT 1+78	RT EOP		162					53				162					
RT 0+51	RT 0+63	Stop Bar					18		36					18				
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>																		
LT 225+48	LT 225+81	Island			114	62			138				114	62				
LT 225+32	LT 225+38	Med Ramp Nose															28	
LT 225+38	LT 225+86	EB Med Curb														3		49
LT 225+38	LT 231+67	WB CC&G		629					208			629				17		
LT 230+95	LT 231+67	WB Med Curb																48
LT 231+67	LT 231+73	Med Ramp Nose															24	
LT 228+12	LT 231+72	WB EOP		580					185			580						
LT 225+82	LT 231+72	WB Ln Line	118	589					194			589						
LT 225+57	LT 225+57	WB Stop Bar					14		28					14				
LT 228+55	LT 228+63	WB Arrows						15.6	16	15.6								
LT 228+85	LT 228+93	WB Arrow						15.6	16	15.6								
LT 225+38	LT 231+67	EB CC&G		629					208			629				32		
LT 225+86	LT 228+26	EB Lt. Turn Ln		62					20			62						
LT 228+26	LT 232+11	EB Lt. Turn Ln	77	385					127			385		11				
LT 228+97	LT 229+05	EB Arrow						15.6	16	15.6								
LT 231+12	LT 231+20	EB Arrow						15.6	16	15.6								
LT 231+15	LT 231+23	WB Arrow						15.6	16	15.6								
RT 231+67	RT 231+67	EB Stop Bar				12			24					12				
RT 225+07	RT 231+66	EB EOP		659					217			659						
RT 225+86	RT 228+25	EB Rt. Turn Ln		62					20			62						
RT 228+25	RT 231+98	EB Rt. Turn Ln	75	373					123			373		10				
RT 232+11	LT 232+11	EB Stop Bar				14			28					14				
RT 229+97	RT 229+05	EB Arrow						15.6	16	15.6								
RT 231+12	RT 231+20	EB Arrows						15.6	16	15.6								
RT 231+98	RT 232+28	Island			109	39			112			109	39					
<b>FOURNIE LANE</b>																		
LT 10+54	LT 10+73	LT EOP		52					17			52						
LT 10+65	LT 10+72	Stop Bar					24		48									24
RT 10+22	RT 10+73	RT EOP		99					33			99						
<b>EASTPORT PLAZA DRIVE</b>																		
RT 47+83	RT 48+64	RT EOP		110					36			110						
RT 47+90	RT 48+02	Stop Bar							36									18
RT 48+18	RT 48+65	Dbl Ln Line	5	48					16			48			3			
RT 48+50	LT 48+58	LI Turn Arrow						15.6	16	15.6								
RT 48+64	LT 48+81	Bike Path			243				243				243					
LT 47+93	LT 47+93	Stop Bar							24									12
LT 47+93	LT 48+66	Lane Line	15	73					24			73						
LT 47+92	LT 48+67	LT EOP		166					55			166						
LT 47+93	LT 48+07	Stop Bar							36									18
LT 48+18	LT 48+18	Stop Bar							24									12
RT 48+78	RT 49+04	RT EOP		26					9			26						
RT 48+79	RT 49+04	Dbl Ln Line	3	25					8			25			3			
LT 48+80	LT 49+04	Lane Line	5	24					8			24						
LT 48+81	LT 49+04	LT EOP		24					8			24						
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>																		
RT 232+64	RT 232+91	Island			88	34			93			88	34					
RT 233+84	RT 242+85	RT EOP		901					297			901						
LT 232+95	LT 242+85	Median	396	3960		255			1562			3960	255		52			
LT 233+04	LT 233+04	Stop Bar							24									12
LT 232+71	LT 232+78	WB Stop Bar					23		46									23
LT 232+71	LT 235+45	WB Ln Line	55	274					90			274						8
LT 233+50	LT 233+58	WB Arrows						15.6	16	15.6								
LT 234+90	LT 234+98	WB Arrow						15.6	16	15.6								
LT 235+45	LT 237+25	WB Ln Line		47					16			47						
LT 233+14	LT 242+85	LT EOP		971					320			971						
<b>TOTAL</b>			<b>748</b>	<b>11054</b>	<b>311</b>	<b>633</b>	<b>177</b>	<b>156</b>	<b>5002</b>	<b>156</b>	<b>11054</b>	<b>311</b>	<b>633</b>	<b>177</b>	<b>103</b>	<b>52</b>	<b>79</b>	<b>132</b>

**PAVEMENT MARKING NOTES:**  
 1. RAISED REFLECTIVE PAVEMENT MARKER QUANTITY INCLUDES THE FOLLOWING TYPES:  
 64 EACH EACH ONE-WAY AMBER MARKERS  
 45 EACH EACH ONE-WAY CRYSTAL MARKERS  
 EACH EACH TWO-WAY AMBER MARKERS  
 109 EACH EACH TOTAL

**EROSION CONTROL SCHEDULE**

STATION	STATION	EROSION CONTROL BLANKET (SQ YD)	TEMP EROS CONTR SEED (POUND)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROS BAR (FOOT)	INLET & PIPE PROTECTION (EACH)
<b>RAMP 4</b>						
RT 1+56						1
LT 0+73	LT 1+78				105	
<b>HORSESHOE LAKE ROAD</b>						
LT 226+40						1
LT 226+50				1		
RT 226+50				1		
LT 226+65						1
LT 226+90						1
LT 227+15						1
LT 227+40						1
LT 227+65						1
LT 227+90						1
LT 228+15						1
LT 228+40						1
LT 228+65						1
LT 228+90						1
LT 229+15						1
LT 229+40						1
LT 229+65						1
LT 229+90						1
LT 230+00						1
LT 230+80						1
LT 231+50				1		
LT 232+92						1
RT 233+02						1
LT 233+50				1		
RT 238+00				1		
RT 239+66						1
LT 239+66						1
RT 1+78 (RAMP 4)	LT 232+17				741	
LT 225+06.5	LT 232+45					
RT 225+06.5	RT 232+12	1566	60			
RT 225+06.5	RT 232+80		20			
RT 225+38	RT 231+87				657	
LT 232+45	LT 242+85		20			
LT 232+71	LT 242+80				1031	
RT 232+80	RT 242+85		20			
RT 233+01	RT 242+90				993	
<b>EASTPORT PLAZA DRIVE</b>						
RT 48+03	RT 48+63					68
LT 48+04	LT 48+67					65
RT 48+81	RT 49+09					28
LT 48+85	LT 49+07					22
<b>TOTALS</b>		<b>1566</b>	<b>120</b>	<b>5</b>	<b>3710</b>	<b>22</b>

**PIPE UNDERDRAIN SCHEDULE**

STATION	STATION	CONC HDWL FOR P DRAIN (EACH)	PIPE UNDERDRAINS 4 (FOOT)	PIPE UNDERDRAINS 4 SP (FOOT)
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>				
LT 226+14	LT 228+90	1	276	20
LT 228+90	LT 231+70	1	280	20
LT 233+20	LT 236+57	1	336	11
LT 236+60	LT 239+60	1	300	9
LT 239+72	LT 242+85	1	313	9
RT 225+06.5	RT 228+38	1	333	10
RT 228+42	RT 231+64	1	322	14
RT 233+32	RT 236+60	1	333	23
RT 236+64	RT 239+60	1	296	4
RT 239+72	RT 242+85	1	313	4
<b>Ramp 4</b>				
LT 0+92	LT 1+54		62	
LT 1+54	LT 1+78	1	23	10
RT 1+60	RT 1+78	1	18	10
<b>TOTAL</b>		<b>12</b>	<b>3205</b>	<b>144</b>

NOTES: 1. SEE STD 601001 FOR MORE INFORMATION.