

PATCHING SCHEDULE

LOCATION	LT/RT	LENGTH (FEET)	WIDTH (FEET)	PAVEMENT PATCHING 12"		
				TYPE 2	TYPE 3	TYPE 4
				(SQ YDS)	(SQ YDS)	(SQ YDS)
5+28	LT	6	12	8		
5+28	RT	6	12	8		
15+84	LT	6	8	5		
18+48	RT	500	3			167
21+12	LT	25	6		17	
47+52	RT	20	13			29
52+80	RT	8	13	12		
53+32	RT	8	6	5		
55+44	RT	8	13	12		
57+05	RT	6	16	11		
58+08	RT	6	13	9		
60+72	RT	15	6	10		
63+36	LT	8	13	12		
63+36	RT	8	13	12		
66+00	LT	6	13	9		
66+00	RT	6	13	9		
67+06	RT	10	13	14		
68+64	LT	30	6		20	
68+68	RT	30	6		20	
73+92	LT	6	13	9		
73+92	RT	8	13	12		
89+76	LT	30	13			43
116+16	LT	20	13			29
121+44	RT	6	13	9		
132+00	RT	8	6	5		
142+56	RT	30	6		20	
147+84	LT	6	13	9		
150+48	LT	10	13	14		
150+48	RT	10	13	14		
151+80	LT	10	13	14		
151+80	RT	10	13	14		
153+12	LT	10	13	14		
153+12	RT	40	6			27
158+40	LT	6	13	9		
158+40	RT	6	13	9		
168+96	LT	8	13	12		
168+96	RT	8	13	12		
174+24	RT	40	6			27
174+24	LT	10	13	14		
184+40	RT	15	13		22	
184+40	LT	15	13		22	
195+36	RT	6	13	9		
195+36	LT	6	13	9		
196+41	LT	6	13	9		
216+48	LT	8	13	12		
217+54	LT	20	13			29
219+12	LT	30	10			33
242+88	RT	10	13	14		
242+88	LT	10	13	14		
258+72	LT	8	13	12		
217+54	LT	20	13			29
219+12	LT	30	10			33
242+88	LT	10	13	14		
242+88	RT	10	13	14		
261+36	RT	6	13	9		
264+00	LT	12	13		17	
269+28	LT	12	13		17	
269+28	RT	12	13		17	
270+34	RT	10	13	14		
270+34	LT	10	13	14		
271+92	RT	200	6			133
271+92	LT	200	6			133

LOCATION	LT/RT	LENGTH (FEET)	WIDTH (FEET)	PAVEMENT PATCHING 12"		
				TYPE 2	TYPE 3	TYPE 4
				(SQ YDS)	(SQ YDS)	(SQ YDS)
273+50	RT	25	6		17	
274+56	LT	6	13	9		
353+76	RT	20	6	13		
380+16	LT	8	13	12		
401+28	LT	20	6	13		
406+56	LT	6	13	9		
406+56	RT	10	13	14		
438+24	LT	15	6	10		
443+52	LT	6	13	9		
464+64	LT	10	13	14		
469+92	LT	8	13	12		
469+92	RT	8	13	12		
485+76	LT	6	13	9		
485+76	RT	6	13	9		
491+04	LT	10	13	14		
496+32	LT	10	13	14		
496+32	RT	10	13	14		
506+88	RT	20	6	13		
509+52	RT	8	13	12		
512+16	LT	10	6	7		
513+22	LT	10	6	7		
514+80	LT	10	6	7		
515+86	RT	6	13	9		
515+86	LT	6	13	9		
533+28	RT	30	6		20	
554+40	LT	10	6	7		
570+24	LT	20	6	13		
570+24	RT	20	6	13		
586+08	LT	10	13	14		
607+20	LT	10	13	14		
644+16	RT	8	13	12		
644+16	LT	8	13	12		
681+12	RT	8	13	12		
681+12	LT	8	13	12		
686+40	LT	15	6	10		
691+68	LT	15	13		22	
694+32	RT	15	6	10		
731+28	LT	6	13	9		
749+76	RT	8	13	12		
749+76	LT	8	13	12		
760+32	LT	50	6			33
770+88	LT	30	13			43
823+68	LT	25	13			36
824+74	LT	10	6	7		
836+88	LT	6	13	9		
860+64	RT	10	13	14		
865+92	LT	30	13			43
897+60	LT	8	6	5		
910+80	RT	10	6	7		
924+00	RT	8	6	5		
929+28	RT	15	6	10		
939+84	RT	10	13	14		
941+16	RT	8	6	5		
942+48	RT	8	6	5		
955+68	RT	10	6	7		
966+24	RT	10	6	7		
SUB--TOTALS				958	231	867
15% FOR ANTICIPATED FAILURES				144	35	130
TOTALS				1102	266	997

FILE NAME = c:\projects\ed01508\plan\pln01508a.dgn	USER NAME = dntelmenjn	DESIGNED - ---	REVISED - ---
		DRAWN - ---	REVISED - ---
	PLOT SCALE = 50.0000 / / IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = 3/21/2008	DATE - ---	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 329	SECTION (125,126)RS-2	COUNTY RANDOLPH	TOTAL SHEETS 34	SHEET NO. 18
CONTRACT NO. 76B38				
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				