

TRAFFIC BARRIER SCHEDULE (CONTINUED)

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	HANDRAIL CONCRETE REM FOOT	STEEL BRIDGE RAIL FOOT	TUBULAR THRIE BEAM RAIL FOOT	TRAFFIC BARRIER TERMINAL					GUARDRAIL MARKERS EACH	TERMINAL MARKERS DIRECT APPLIED EACH	REMARKS
						TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 6A EACH	TYPE 6B EACH	TYPE 9 EACH			
JOHNSON COUNTY													
044 - 0001													
RT 836+66.00 TO 837+16.00						1						1	TERMINAL REPLACEMENT
RT 837+16.00 TO 838+41.00	43.00	125.00									2		INSTALL WITH 1:40 FLARE
RT 838+41.00 TO 838+66.00	25.00									1			TERMINAL REPLACEMENT
RT 838+66.00 TO 838+91.00	25.00				25.0								THRIE BEAM RETROFIT
RT 838+91.00 TO 839+41.00					50.0								THRIE BEAM RETROFIT
RT 839+41.00 TO 839+66.00	25.00				25.0								THRIE BEAM RETROFIT
RT 839+66.00 TO 839+91.00	25.00									1			TERMINAL REPLACEMENT
RT 839+91.00 TO 840+53.50	42.00	62.50									1		INSTALL WITH 1:40 FLARE
RT 840+53.50 TO 841+03.50						1						1	TERMINAL REPLACEMENT
LT 836+98.50 TO 837+48.50						1						1	TERMINAL REPLACEMENT
LT 837+48.50 TO 838+11.00	47.00	62.50									1		INSTALL WITH 1:40 FLARE
LT 838+11.00 TO 838+36.00	25.00									1			TERMINAL REPLACEMENT
LT 838+36.00 TO 838+61.00	25.00				25.0								THRIE BEAM RETROFIT
LT 838+61.00 TO 839+11.00					50.0								THRIE BEAM RETROFIT
LT 839+11.00 TO 839+36.00	25.00				25.0								THRIE BEAM RETROFIT
LT 839+36.00 TO 839+61.00	25.00									1			TERMINAL REPLACEMENT
LT 839+61.00 TO 840+86.00	39.00	125.00									2		INSTALL WITH 1:40 FLARE
LT 840+86.00 TO 841+36.00						1						1	TERMINAL REPLACEMENT
SUBTOTALS:	371.0	375.0	0	0	200	4	0	0	0	4	6	4	
TOTALS:	863.0	1775.0	208.0	208.0	640.0	20	2	8	2	8	32	20	