SEEDING & EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	SEEDING AREA (FOR INFO ONLY)	SEEDING CLASS 2	SEEDING CLASS 7 (TEMPORARY)	NITROGEN FERTILIZER NUTRIENTS		PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	AGRICULTURAL GROUND LIMESTONE	EROSION CONTROL BLANKET	MULCH METHOD 2 FOR CLASS 7	TEMP DITCH CHECK
				CLASS 2	CLASS 7						
	SQ FEET	ACRE	ACRE	POUND	POUND	POUND	POUND	TON	SQ YD	ACRE	EACH
SALINE COUNTY											
LOCATION 1											
RT 53+41 TO 53+64	250	0.01	0.01	1.02	0.45	1.02	1.02	0.02	28	0.01	
LT 53+42 TO 53+64	343	0.01	0.01	1.02	0.45	1.02	1.02	0.02	38	0.01	
LOCATION 2											
RT 160+87 TO 162+73	4604	0.13	0.13	11.25	5.00	11.25	11.25	0.25	512	0.13	1
LT 161+29 TO 162+35	1068	0.03	0.03	3.07	1.36	3.07	3.07	0.07	119	0.03	1
LOCATION 3											
RT 165+62 TO 166+62	1741	0.05	0.05	4.09	1.82	4.09	4.09	0.09	193	0.05	
LT 165+65 TO 166+00	704	0.02	0.02	2.05	0.91	2.05	2.05	0.05	78	0.02	
LOCATION 4											
RT 234+13 TO 234+73	1103	0.03	0.03	3.07	1.36	3.07	3.07	0.07	123	0.03	
LT 234+09 TO 234+72	1267	0.03	0.03	3.07	1.36	3.07	3.07	0.07	141	0.03	
LOCATION 5											
RT 240+26 TO 241+43	2484	0.07	0.07	6.14	2.73	6.14	6.14	0.14	276	0.07	
LT 240+03 TO 240+65	1079	0.03	0.03	3.07	1.36	3.07	3.07	0.07	120	0.03	
LOCATION 6											
LT 665+37 TO 670+64	7629	0.20	0.20	18.41	8.18	18.41	18.41	0.41	848	0.20	
SALINE SUBTOTALS		0.63	0.63	56.3	25.0	56.3	56.3	1.3	2475	0.63	2
JOHNSON COUNTY											
LOCATION 7											
LT 857+28 TO 863+88	8614	0.23	0.23	20.46	9.09	20.46	20.46	0.45	957	0.23	
LT 865+87 TO 869+32	4744	0.13	0.13	11.25	5.00	11.25	11.25	0.25	527	0.13	
JOHNSON SUBTOTALS		0.35	0.35	31.7	14.1	31.7	31.7	0.7	1484	0.35	0
TOTALS		1.0	1.0	88	39	88	88	2	3959	1.0	2
				127							

FILE NAME = c:\projects\d901907\d901907sht.m32	USER NAME = thomash	DESIGNED - ___	REVISED - ___
		DRAWN - ___	REVISED - ___
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ___	REVISED - ___
	PLOT DATE = 3/18/2008	DATE - _____	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES – SEEDING & EROSION CONTROL

SCALE: NONE | SHEET NO. __ OF ___ SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
881	D9 SAFETY FY08-1	VARIOUS	64	12
		CONTRACT NO. 78038		

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT