CONTRACT NO. 78039

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	29	11
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* (1-2)RS-3,(1-3)RS-2

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

STATION TO STATION				THERMOPLASTIC PVT MRKG - LINE 4"			THPL PVT MRK - LINE 24 INCH	THPL PVT MRK - LTR & SYMB	POLYUREA PVT MRK - LINE 4 INCH	POLYUREA PVT MRK - LINE 24 INCH	TEMPORARY			NOTES
				4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH					4 INCH	24 INCH	LETTERS & SYMBOLS	
				FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	
IL 13 - Division St. to Route 148														
RURAL LIMITS														
LEFT	467+57.00	TO	492+99.00		2542						2542			Edgeline
	467+57.00	TO	574+20.99			2666					2666			
LEFT	489+83.00	TO	492+99.00	316							316			Main St. Turn Lane
LEFT	489+93.00							20.8					20.8	Only
LEFT	490+21.00							15.6					15.6	Left Turn Arrow
LEFT	493+99.00	TO	520+22.00		2623						2623			Edgeline
LEFT	516+97.00	TO	520+22.00	325							325			Wolf Creek Turn Lane
LEFT	517+07.00							20.8					20.8	Only
LEFT	517+35.00							15.6					15.6	Left Turn Arrow
LEFT	521+33.00	TO	559+96.00		3863						3863			Edgeline
LEFT	556+66.00	TO	559+96.00	330							330			Samuel Rd. Turn Lane
LEFT	556+76.00							20.8					20.8	Only
LEFT	557+04.00							15.6					15.6	Left Turn Arrow
LEFT	560+87.00	TO	574+20.99		1334						1334			Edgeline
RURAL SUBTOTALS				971	10362	2666	0	109.2			13999	0.0	109.2	
URBAN LIMITS BEGIN STA. 574+20.99														
URBAN LIMITS														
LEFT	574+20.99	TO	586+12.00		1191						1191			Edgeline
	574+20.99	TO	615+01.50			1020					1020			
LEFT	583+97.00	TO	586+12.00	215							215			Briggs Rd. Turn Lane
LEFT	584+07.00							20.8					20.8	Only
LEFT	584+35.00							15.6					15.6	Left Turn Arrow
LEFT	587+07.23	TO	615+01.50		2795						2795			Edgeline
EQ STA 615+01.5 (BK) = STA. 615+05.84 (AH)														
LEFT	615+05.84	TO	620+45.00		539	135					674			Edgeline
	620+45.00	TO	626+57.00						153.0		0			
	626+57.00									24.0		24.0		Stop Bar - Thru Lanes
URBAN SUBTOTALS				215	4525	1155	0	36.4	153.0	24.0	5895	24.0	36.4	
RIGHT	467+57.00	TO	492+73.00	2516							2516			Edgeline
RIGHT	493+29.00				100		24				100	24		Main St. - Stop Bar and Dbl Yellow
RIGHT	493+84.00	TO	519+85.00	2601							2601			Edgeline
RIGHT	520+59.00				246		36				246	36		Wolf Creek - Stop Bar and Dbl Yellow
RIGHT	521+78.00	TO	559+75.00	3797							3797			Edgeline
RIGHT	560+35.00				102		24				102	24		Samuel Rd. - Stop Bar and Dbl Yellow
RIGHT	560+89.00	TO	574+20.99	1332							1332			Edgeline
RURAL SUBTOTALS				10246	448	0	84	0.0	0.0	0.0	10694	84	0.0	
RIGHT	574+20.99	TO	585+80.00	1159							1159			Edgeline
RIGHT	586+47.00				100		24				100	24		Briggs Rd. - Stop Bar and Dbl Yellow
RIGHT	587+06.00	TO	615+01.50	2796							2796			Edgeline
RIGHT	615+05.84	TO	620+45.00	539							539			Edgeline
RIGHT	623+67.00	TO	625+84.00						217.0		0			Right Turn Lane Line
URBAN SUBTOTALS				4,494	100	0	24	0.0	217.0		4594	24	0.0	
RURAL TOTALS				11,217	10,810	2,666	84	109.2	0.0	0.0	24,693	84	109.2	
URBAN TOTALS				4,709	4,625	1,155	24	36.4	370.0	24.0	10,489	48	36.4	
TOTALS					35,182		108	145.6	370.0	24.0	35,182	132	145.6	

PLOT DATE = 3/19/2008
FILE NAME = c:\pw_work\pw_{illegible}\d0{illegible}70.sa.sa32
PLOT SCALE = 100.0824 ' / IN.
USER NAME = mccorder

SCHEDULE: THERMOPLASTIC PAVEMENT MARKING