

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON CO.
				ROADWAY RURAL 80% FED/20% ST
CONSTRUCTION TYPE CODE				1000
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1,865	1,865
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	26,782	26,782
40600300	AGGREGATE (PRIME COAT)	TON	447	447
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	6,335	6,335
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	158	158
40600990	TEMPORARY RAMP	SQ YD	336	336
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	13,025	13,025
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	387	387
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	132,358	132,358
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	14,241	14,241
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	101	101
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	2,041	2,041
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	18	18
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,064	2,064
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,263	1,263
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7
63200310	GUARDRAIL REMOVAL	FOOT	225	225
63300725	STEEL PLATE BEAM GUARD RAIL (SHORT RADIUS)	FOOT	40	40
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13,840	13,840
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4	122.4
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	128,595	128,595
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	47,650	47,650
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4	122.4
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	128,595	128,595
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	24	24
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	635	635
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	20	20
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	635	635
X0322729	MATERIAL TRANSFER DEVICE	TON	19,360	19,360
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

**SPECIALTY ITEMS*

FILE NAME = c:\projects\78044\78044.mso.dgn	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 100,0000' / IN.	CHECKED -	REVISED -	REVISED -			726	(119,120)RS-3	JEFFERSON	16	4	
PLOT DATE = 9/17/2008	DATE -	REVISED -	REVISED -			CONTRACT NO. 78044					
						SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		FED. ROAD DIST. NO.