

RESURFACING AND SHOULDER SCHEDULE

LOCATION	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	PRIME COAT		SHOULDERS		HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT
			POLYMERIZED BITUMINOUS MATERIALS	AGGREGATE	AGGREGATE TYPE B	HOT-MIX ASPHALT, 3 1/4"						
STATION TO STATION	TON	TON	GAL	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
STA 471+90 TO STA 472+00											43	
STA 471+90 TO STA 473+20												550
STA 471+90 TO STA 688+75 (OUTSIDE SHOULDER)			2169	37	583	24095						
STA 471+90 TO STA 688+75 (INSIDE SHOULDER)			868	15	1168	9638						
STA 471+90 TO STA 688+75 (DRIVING LANE)		2433	2603	44								
STA 471+90 TO STA 688+75 (PASSING LANE)		2433	2603	44								
STA 472+50 TO STA 510+00 (DRIVING LANE)	628											
STA 473+20 TO STA 510+00							9814					
STA 503+00 (APRON AT TURN AROUND)		13										
STA 472+50 TO STA 688+35 (PASSING LANE)	3622											
STA 510+00 TO STA 600+00 (PASSING LANE)							12000					
STA 510+00 TO STA 600+00 (DRIVING LANE)	3360								12000			
STA 600+00 TO STA 611+64.5							3,106					
STA 600+00 TO STA 688+35 (DRIVING LANE)	1482											
STA 611+64.5 TO STA 612+94.5												
STA 612+94.5 TO STA 614+54.5 (SHOULDERS)									249			
STA 612+94.5 TO STA 614+54.5									427			
STA 614+54.5 TO STA 615+84.5												
STA 615+84.5 TO STA 688+35							19,335					
STA 688+35 TO STA 688+75												170
STA 688+65 TO STA 688+75											43	
TOTALS	9,092	4,879	8,243	140	1,751	33,733	44,255	249	12,427	1,098	86	720

TRAFFIC BARRIER SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TERMINAL		GUARDRAIL MARKER, TYPE B	TERMINAL MARKERS DIRECT APPLIED
			TYPE 1 (SPECIAL) TANGENT	TYPE 6B		
STATION TO STATION	FOOT	FOOT	EACH	EACH	EACH	EACH
STA 610+55.84 RT						1
STA 610+55.84 RT TO STA 611+05.84 RT			1			
STA 611+05.84 RT TO STA 613+30.84 RT		225			3	
STA 611+61 RT TO STA 613+93 RT	232					
STA 613+30.84 RT TO STA 613+87.10 RT				1		
TOTALS	232	225	1	1	3	1

RIPRAP SCHEDULE

LOCATION	LENGTH OF STONE RIPRAP DITCH*	LENGTH OF STONE RIPRAP DITCH LINING*	STONE RIPRAP DITCH	STONE RIPRAP CLASS A3
STATION TO STATION	FOOT	FOOT	TON	SQ YD
STA 471+90 RT TO STA 472+87 RT	104		58	
STA 477+11 RT TO STA 478+12 RT	107		60	
STA 478+12 RT TO STA 478+80 RT		70		78
STA 502+65 RT TO STA 503+37 RT	84		47	
STA 503+37 RT TO STA 503+65 RT		30		34
STA 626+28 RT TO STA 627+28 RT	100		56	
STA 632+95 RT TO STA 636+58 RT	411		229	
STA 636+58 RT TO STA 641+25 RT		467		519
STA 660+62 RT TO STA 661+78 RT	120		67	
TOTALS	926	567	517	631

* NOT A PAY ITEM - FOR INFORMATION ONLY