

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE		J000	Y031-1F
		UNIT	URBAN TOTAL QUANTITIES	ROADWAY 100% STATE	TRAFFIC SIGNALS 100% STATE
* X0300737	RADIO TRANSCEIVER	EACH	1		1
X7030010	TEMPORARY PAVEMENT MARKING TAPE, 6 INCH (BLACK)	FOOT	1187	1187	
* X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1		1
Z0017100	DOWEL BARS	EACH	84	84	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	40	40	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	30	30	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	30	30	
20200100	EARTH EXCAVATION	CU YD	126	126	
20400800	FURNISHED EXCAVATION	CU YD	328	328	
20800150	TRENCH BACKFILL	CU YD	33	33	
25000115	SEEDING, CLASS 1B	ACRE	0.25	0.25	
25000350	SEEDING, CLASS 7	ACRE	0.25	0.25	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
25100630	EROSION CONTROL BLANKET	SQ YD	516	516	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100107	STONE RIP RAP, CLASS A4	SQ YD	19	19	
28200200	FILTER FABRIC	SQ YD	19	19	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1416	1416	
40600990	TEMPORARY RAMP	SQ YD	52	52	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1267	1267	
42001200	PAVEMENT FABRIC	SQ YD	26	26	
42001300	PROTECTIVE COAT	SQ YD	1359	1359	
44000100	PAVEMENT REMOVAL	SQ YD	953	953	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	275	275	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	8	8	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	26	26	
44213200	SAW CUTS	FOOT	178	178	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	221	221	
542A0259	PIPE CULVERTS, CLASS A, TYPE 1 54"	FOOT	90	90	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	118	118	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	1.42	1.42	
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	330	330	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	

FILE NAME = c:\projeoat\78055\d978055_sht.mso.dgn	USER NAME = poosl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE. 873	SECTION (28-5) TS-3,N-1	COUNTY FRANKLIN	TOTAL SHEETS 38	SHEET NO. 3	
PLOT SCALE = 50.0000' / IN.						SCALE:		SHEET NO. OF SHEETS		STA. TO STA.	
PLOT DATE = 3/19/2008								FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
DATE -								CONTRACT NO. 78055			

\*SPECIALTY ITEMS