

SUMMARY OF QUANTITIES (CONTINUED)

CODE NO.	ITEM	CONSTRUCTION TYPE CODE		J000	Y031-IF
		UNIT	URBAN TOTAL QUANTITIES	ROADWAY 100% STATE	TRAFFIC SIGNALS 100% STATE
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.75	0.25
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5	5	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	70.6	70.6	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1039	1039	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	347	347	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	65	65	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1983	1983	
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12		12
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	70.6	70.6	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1039	1039	
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	347	347	
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	65	65	
78300105	PAVEMENT MARKING REMOVAL	FOOT	171	171	
80300100	LOCATING UNDERGROUND CABLE	FOOT	25		25
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1		1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	378		378
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	77		77
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	20		20
81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT	63		63
81021580	CONDUIT, AUGERED 3 1/2" DIA., PVC	FOOT	63		63
81400100	HANDHOLE	EACH	2		2
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	475		475
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10	FOOT	456		456
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	4		4
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
86600010	GULFBOX JUNCTION	EACH	7		7
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	86		86
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1030		1030
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2058		2058
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1		1
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1		1
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	28		28

SPECIALTY ITEMS

FILE NAME = c:\projects\78055\78055_sht_mso.dgn	USER NAME = poeal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 873	SECTION (28-5) TS-3,N-1	COUNTY FRANKLIN	TOTAL SHEETS 38	SHEET NO. 4	
PLOT SCALE = 5/8" = 1' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 78055			
PLOT DATE = 3/19/2008	DATE -	REVISED -									
							ILLINOIS FED. AID PROJECT				