



- NOTES:
1. THE PAY ITEM FOR REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT SHALL INCLUDE THE REMOVAL OF THE FOLLOWING ITEMS:
COMBINATION MAST ARM ASSEMBLY AND POLE WITH LUMINAIRES
STA 676+23 40' RT, 36' LONG
STA 677+31 41' RT, 28' LONG
TYPE A FOUNDATION STA 677+07, 45' RT
CONCRETE HANDHOLES
STA 676+18, 44' RT
STA 677+169, 40' RT
CABINET WITH TYPE IV CONTROLLER STA 0+68, 50' RT
 2. WHERE ELEVATIONS ARE NOT SHOWN, MATCH EXISTING GROUND.
 3. STATIONS AND OFFSETS OF CABLE PULL POINTS ARE APPROXIMATE AND WILL HAVE TO BE LOCATED IN THE FIELD.

FILE NAME =
c:\projects\78055\78055-ts.dgn

USER NAME = neasp
DESIGNED -
DRAWN -
PLOT SCALE = 30,000' / IN.
PLOT DATE = 3/18/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PROPOSED TRAFFIC SIGNAL AND LIGHTING PLAN

| | | | | |
|---------------------|-----------------|----------|---------------------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 873 | (28-5) TS-3,N-1 | FRANKLIN | 38 | 18 |
| FED. ROAD DIST. NO. | | | ILLINOIS FED. AID PROJECT | |
| CONTRACT NO. 78055 | | | | |

SCALE: SHEET NO. OF SHEETS STA. TO STA.