

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
369	00-00018-00-PV	COOK	20	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 83897

EARTHWORK SCHEDULE

STATION	EARTH EXCAVATION	EARTH EXCAVATION	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) *
	**	ADJUSTED FOR SHRINKAGE (15%)		
	CY	CY	CY	CY
20+85.82	36.9	31.4	1.9	29.5
21+00	141.9	120.6	10.0	110.6
21+50	153.1	130.2	8.1	122.0
22+00	150.0	127.5	8.4	119.1
22+50	136.5	116.0	6.4	109.6
23+00	144.7	123.0	1.8	121.3
23+50	170.4	144.8	0.3	144.5
24+00	168.7	143.4	0.1	143.3
24+50	161.9	137.6	2.1	135.4
25+00	156.7	133.2	3.0	130.2
25+50	133.4	113.4	12.3	101.1
26+00	105.8	90.0	43.2	46.7
26+50	99.0	84.1	46.9	37.2
27+00	121.2	103.0	44.3	58.8
27+50	152.7	129.8	31.8	98.0
28+00	161.5	137.3	13.1	124.1
28+50	145.9	124.0	31.1	92.9
29+00	151.4	128.7	22.7	106.0
29+50	153.6	130.6	17.8	112.8
30+00	134.9	114.7	34.4	80.3
30+50	81.4	69.2	15.6	53.6
30+80.07	58.4	49.7	4.5	45.1
31+00	144.2	122.5	8.9	113.7
31+50	138.9	118.1	5.6	112.4
32+00	196.9	167.3	0.9	166.4
32+50	0.0	0.0	0.0	0.0
TOTAL=	3400.0	2889.9	375.3	2514.6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
75th STREET
EARTHWORK SCHEDULE

SCALE: VERT. N.T.S.
HORIZ.
DATE 3/31/2008

DRAWN BY EDT
CHECKED BY LMF