

SUMMARY OF QUANTITIES

| CODE | PAY ITEM | UNIT | TOTAL QUANTITY | H22 | 07C |
|------------|--|------|----------------|----------------------------------|-----------------------|
| | | | | Y003 80% FEDERAL 20% LOCAL | Y003 100% LOCAL |
| 20200100 | EARTH EXCAVATION | CUYD | 45 | 45 | 0 |
| * 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQYD | 200 | 200 | 0 |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT | LBS | 3 | 3 | 0 |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | LBS | 3 | 3 | 0 |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT | LBS | 3 | 3 | 0 |
| * 25200100 | SODDING | SQYD | 200 | 200 | 0 |
| * 25300500 | TOPSOIL FOR PLANTING | CUYD | 45 | 45 | 0 |
| 42101300 | PROTECTIVE COAT | SQYD | 3730 | 3730 | 0 |
| 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7" | SQYD | 525 | 525 | 0 |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8" | SQYD | 200 | 200 | 0 |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK, 5" | SQFT | 27500 | 27500 | 0 |
| 42400800 | DETECTABLE WARNINGS | SQFT | 1100 | 1100 | 0 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQYD | 525 | 525 | 0 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 520 | 520 | 0 |
| 44000600 | SIDEWALK REMOVAL | SQFT | 39500 | 39500 | 0 |
| 56500600 | DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED | EACH | 7 | 7 | 0 |
| 60266600 | VALVE BOXES TO BE ADJUSTED | EACH | 1 | 1 | 0 |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 2 | 2 | 0 |
| 60604100 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED) | FOOT | 520 | 520 | 0 |
| 67100100 | MOBILIZATION | LSUM | 1 | 1 | 0 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | LSUM | 1 | 1 | 0 |
| * 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 1 | 1 | 0 |
| * 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 1350 | 1350 | 0 |
| * 81019000 | CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL | FOOT | 60 | 60 | 0 |
| * 81400115 | HANDHOLE TO BE ADJUSTED | EACH | 8 | 8 | 0 |
| * 81603090 | UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE | FOOT | 7520 | 7520 | 0 |
| * 81702440 | ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3-1/C NO. 1/0 | FOOT | 75 | 75 | 0 |
| * 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 5700 | 5700 | 0 |
| * 82500505 | LIGHTING CONTROLLER, SPECIAL | EACH | 1 | 1 | 0 |
| * 84200600 | REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE | EACH | 37 | 0 | 37 |
| * 84200700 | LIGHTING FOUNDATION REMOVAL | EACH | 37 | 0 | 37 |

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES

| CODE | PAY ITEM | UNIT | TOTAL QUANTITY | Y003 | Y003 |
|------------|---|--------|----------------|--------------------------|---------------|
| | | | | 80% FEDERAL 20% LOCAL | 100% LOCAL |
| * 84500110 | REMOVAL OF LIGHTING CONTROLLER | EACH | 1 | 0 | 1 |
| * 84500130 | REMOVAL OF LIGHTING CONTROLLER FOUNDATION | EACH | 1 | 0 | 1 |
| * A2000724 | TREE, ACER PLATANOIDES COLUMNARE (COLUMNAR NORWAY MAPLE), 3" CALIPER, BALLED AND BURLAPPED | EACH | 9 | 9 | 0 |
| * A2004724 | TREE, GLEDITSIA TRIACANTHOS INTERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEY LOCUST) 3" CALIPER, BALLED AND BURLAPPED | EACH | 8 | 8 | 0 |
| * A2008124 | TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED | EACH | 9 | 9 | 0 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQFT | 103 | 103 | 0 |
| * X0323574 | MAINTENANCE OF LIGHTING SYSTEM | CAL MO | 6 | 0 | 6 |
| * XX003059 | DECORATIVE BRICK SIDEWALK | SQFT | 11800 | 11800 | 0 |
| * XX005878 | CAST IRON TREE GRATES | EACH | 26 | 26 | 0 |
| * XX006937 | GROUND ROD, 5/8" X 10 FT | EACH | 60 | 60 | 0 |
| * XX007000 | PORTLAND CEMENT CONCRETE BASE COURSE, 3" | SQFT | 11800 | 11800 | 0 |
| XX007463 | DECORATIVE LIGHT POLE, CONCRETE, 30' MOUNTING HEIGHT WITH 1-6' MAST ARM AND 1-3' MAST ARM | EACH | 60 | 0 | 60 |
| XX007464 | DECORATIVE LUMINAIRE, METAL HALIDE, HORIZONTAL MOUNT 150 WATT | EACH | 46 | 0 | 46 |
| * XX004716 | LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 175 WATT | EACH | 8 | 0 | 8 |
| * XX006511 | LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 400 WATT | EACH | 6 | 0 | 6 |
| * XX004714 | LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 70 WATT | EACH | 60 | 60 | 0 |

* DENOTES SPECIALTY ITEM

Drawing File: W:\Projects\65506153 - Lake St Streetscape\Sum_Quantities.dwg Feb 20, 2008 - 4:28pm



♦ Civil Engineers
 ♦ Municipal Consultants
 ♦ Established 1911
 9933 Roosevelt Road
 Westchester, Illinois 60154-2780
 Phone: 708/865-0300
 Fax: 708/865-1212

**LAKE STREET STREETScape
VILLAGE OF MAYWOOD, ILLINOIS**

SUMMARY OF QUANTITIES

| | | |
|-------------|--------------------|--------------------------------------|
| SCALE: | NONE | SHEET 4 OF 22 |
| DRAWN BY: | LEV ECW | |
| BOOK NO.: | SDR33/1480/1484/LS | |
| DATE: | 02/20/2008 | |
| E.H.E. NO.: | 565-06-15302 | |