CONTRACT NO. 85427

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FED 20% CITY J000 P.C. CONCRETE	80% FED 20% OTHER Y046 P.C. PATH	80% FED 20% OTHER SFTY-2A STRUCTURES	80% FED 20% CITY Y007 MINOR STRUCT.	80% FED 20% OTHER Y007 MINOR STRUCT.	80% FED 20% CITY Y030-1E HWY. LIGHTING	80% FED 20% OTHER Y030-1E HWY. LIGHTING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	428	69	359					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	497	267	230					
20200100	EARTH EXCAVATION	C.Y.	1,980	1,240	740					
20700220	POROUS GRANULAR EMBANKMENT	C.Y.	310		310					
20800150	TRENCH BACKFILL	C.Y.	646.6	646.6						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	S.Y.	2,212	2,212						
25000300	SEEDING, CLASS 3	ACRE	0.11	0.02	0.09					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8	2	6					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	2	6					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8	2	6					
25100115	MULCH, METHOD 2	ACRE	0.79	0.21	0.58					
25100635	HEAVY DUTY EROSION CONTROL BLANKET	S.Y.	533	97	436					
25100900	TURF REINFORCEMENT MAT	S.Y.	56.0	11.1	44.9					
25101504	WOOD CHIP MULCH, 4"	S.Y.	262		262					
25200100	SODDING	S.Y.	1,468.0	953.5	514.5					
25200200	SUPPLEMENTAL WATERING	UNIT	30.8	20.0	10.8					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	316	84	232					
28000300	TEMPORARY DITCH CHECKS	EACH	4		4					
28000400	PERIMETER EROSION BARRIER	FOOT	1,939	405	1,534					
28000500	INLET AND PIPE PROTECTION	EACH	8	6	2					
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	716	716						
35100100	AGGREGATE BASE COURSE, TYPE A	TON	79	79						
*SPECIALTY ITEMS										

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALEL$
USER NAME = $USER$