CONTRACT NO. 85427

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

44000600 SIDEWALK REMOVAL		S.F.
11TH STREET		
RT. STA. 1+74		22
RT. STA. 4+09		19
LT./RT. STA. 5+21		115
LT./RT. STA. 5+55		126
LT. STA. 6+00 TO 6+20		342
RT. STA. 6+21		60
MULTI-USE PATH		
LT./RT. STA. 105+25 TO 107+98.17		1,868
104' RT. STA. 107+54 TO 169' RT. STA. 107+33		397
162' RT. STA. 107+63 TO 246' RT. STA. 107+52		1,071
	TOTAL	4,020
44213200 SAW CUTS		FT.
11TH AVENUE		
LT./RT. STA. 6+23.92		63
37TH STREET		
LT./RT. STA. 9+87 TO 9+91.8		35
	TOTAL	98
50901760 PIPE HANDRAIL		FOOT
DORMITORY STAIRS		
LT. STA. 0+22.11 TO 0+31.31		11.4
RT. STA. 0+22.11 TO 0+31.31		11.4
	TOTAL	22.8
54200640 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 15"		FOOT
NATURE TRAIL		
LT. & RT. STA. 200+10		10
LT. & RT. STA. 202+32		23
LT. STA. 202+32-202+77		45
	TOTAL	78
54213459 END SECTIONS 24"		EACH
11TH AVENUE		
90' LT. STA. 2+14.5		1
	TOTAL	1
54213657 PRECAST REINORCED CONCRETE FLARED END SECTIONS 12"		EACH
MULTI-USE PATH		
19' LT. STA. 106+91		1
	TOTAL	1
54215550 METAL END SECTIONS, 15"		EACH
NATURE TRAIL		
LT. & RT. STA. 200+10		2
LT. & RT. STA. 202+32		2
LT. STA. 202+30		1
	TOTAL	5
550A0070 STORM SEWERS, CLASS A, TYPE 1 15"		FT.
37TH STREET		
RT. STA. 9+93 TO 10+32		38
	TOTAL	38
550A0340 STORM SEWERS, CLASS A, TYPE 2, 12"		FT.
11TH AVENUE		
LT./RT. STA. 2+85		24
MULTI-USE PATH		
LT. & RT. 107+17		38
LT. 107-09 TO 106+97		16
	TOTAL	78
55100700 STORM SEWER REMOVAL 15"		FT.
37TH STREET		
21' RT. STA. 9+93 TO 12' RT. STA. 10+54		68
	TOTAL	68
55101100 STORM SEWER REMOVAL 21"		FT.
12' RT. STA. 10+54 (37TH ST) TO 37' LT. STA. 2+75 (11TH AVE)		118
	TOTAL	118
56100500 WATER MAIN 4"		FT.
11TH AVENUE		
RT. STA. 5+42.5		6
	TOTAL	6
56100600 WATER MAIN 6"		FT.
11TH AVENUE		
RT. STA. 6+08 TO 6+18		10
RT. STA. 5+40		6
37TH STREET		
LT./RT. STA. 9+98		6
	TOTAL	22
56100700 WATER MAIN 8"		FT.
11TH AVENUE		
STA. 0+86 TO 4+92		413
LT./RT. STA. 1+91		57
LT./RT. STA. 4+92		29
37TH STREET		
STA. 9+89 TO 11+13.5		145
	TOTAL	644
56400500 FIRE HYDRANTS TO BE REMOVED		EACH
11TH AVENUE		
27' RT. STA. 6+18		1
	TOTAL	1
56400510 FIRE HYDRANTS TO BE REMOVED AND REPLACED		EACH
37TH STREET		
16.7' LT. STA. 9+98		1
	TOTAL	1
56400600 FIRE HYDRANTS		EACH
11TH AVENUE		
28' RT. STA. 6+08		1
	TOTAL	1
60100985 PIPE DRAINS 24"		FT.
11TH AVENUE		
22.7' LT. STA. 2+93		106
	TOTAL	106
60107600 PIPE UNDERDRAINS 4"		FOOT
11TH AVENUE		
LT. STA. 2+72-2+82		10
RT. STA. 2+72-2+82		10
LT. STA. 2+88-2+98		10
RT. STA. 2+88-2+98		10
37TH STREET		
LT. STA. 10+19-10+29		10
RT. STA. 10+19-10+29		10
LT. STA. 10+35-10+45		10
RT. STA. 10+35-10+45		10
	TOTAL	80
60218400 MANHOLES, TYPE A 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID		EACH
MULTI-USE PATH		
19' LT. STA. 107+10		1
	TOTAL	1
60223800 MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID		EACH
11TH AVENUE		
22.7' LT. STA. 2+93		1
	TOTAL	1
60240301 INLET TYPE B, TYPE 8 GRATE		EACH
MULTI-USE PATH		
18' RT. STA. 107+25		1
	TOTAL	1
60500060 REMOVING INLETS		EACH
37TH STREET		
12' LT. STA. 10+54		1
	TOTAL	1
60600105 CONCRETE CURB		FOOT
DORMITORY STAIRS		
LT. STA. 0+31.31 TO 0+43.08		14.1
RT. STA. 0+31.31 TO 0+43.08		9.5
	TOTAL	23.6
60900515 CONCRETE THRUST BLOCKS		EACH
11TH AVENUE		
82' LT. STA. 2+24 (24" PIPE DRAIN)		1
NATURE TRAIL		
10.5' LT. STA. 262+31.35 (15" PIPE DRAIN)		1
	TOTAL	2
61000215 PORTLAND CEMENT CONCRETE SHOULDERS		S.Y.
MULTI-USE PATH		
LT. STA. 101+25 TO 102+74.18		49.7
	TOTAL	49.7
67100100 MOBILIZATION		L.SUM
ENTIRE PROJECT		1
	TOTAL	1
70103700 TRAFFIC CONTROL COMPLETE		L.SUM
ENTIRE PROJECT		1
	TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $FSCALE$
USER NAME = $USER$