

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00174-00-BT	ROCK ISLAND	112	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

XX005425 LANDSCAPE BOLLARDS	EACH	
11TH AVENUE		
LT. STA. 1+25	1	
LT. STA. 1+46	1	
LT. STA. 1+66	1	
LT. STA. 1+86	1	
LT. STA. 2+06	1	
LT. STA. 2+26	1	
LT. STA. 2+46	1	
LT. STA. 2+65	1	
LT. STA. 2+86	1	
LT. STA. 3+06	1	
LT. STA. 3+28	1	
LT. STA. 3+49	1	
LT. STA. 3+69	1	
LT. STA. 3+90	1	
TOTAL	14	
XX005763 CATCH BASINS, DOUBLE	EACH	
11TH AVENUE		
13.58' LT. STA. 2+85	1	
13.58' RT. STA. 2+85	1	
37TH STREET		
12.58' LT. STA. 10+32	1	
12.58' RT. STA. 10+32	1	
TOTAL	4	
XX005764 CATCH BASINS, SINGLE	EACH	
11TH AVENUE		
13.58' RT. STA. 3+88	1	
TOTAL	1	
XX005782 DUCTILE IRON WATER MAIN FITTINGS REDUCER 12" X 8"	EACH	
11TH AVENUE		
13' RT. STA. 4+92	1	
TOTAL	1	
XX005784 DUCTILE IRON WATER MAIN FITTINGS TEE 12" X 4"	EACH	
11TH AVENUE		
12' RT. STA. 5+42.5	1	
TOTAL	1	
XX005788 DUCTILE IRON WATER MAIN FITTINGS TEE 8" X 8"	EACH	
11TH AVENUE		
15.58' LT. STA. 1+91	1	
15.58' LT. STA. 3+52	1	
TOTAL	2	
XX006179 SANITARY MANHOLE REMOVAL & REPLACEMENT	EACH	
11TH AVENUE		
2.5' RT. STA. 0+60	1	
37TH STREET		
20.2' LT. STA. 10+94.6	1	
TOTAL	2	
X0300558 SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FT.	
11TH AVENUE		
3.5' RT. STA. 0+60 TO 19.6' RT. STA. 3+42	273	
37TH STREET		
0.5' LT. STA. 10+00.9 TO 20.2' LT. STA. 10+94.6	101	
TOTAL	374	
X0321473 PIPE ELBOW, 15"	EACH	
NATURE TRAIL		
LT. STA. 202+31	1	
TOTAL	1	

X0322033 STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FT.	
11TH AVENUE		
LT. STA. 2+85 TO 2+93	8	
LT. STA. 2+93 TO RT. STA. 3+88	98	
37TH STREET		
LT./RT. STA. 10+32	23	
TOTAL	129	
X0322034 STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FT.	
37TH STREET		
RT. STA. 10+32 (37TH ST.) TO LT. STA. 2+93 (11TH AVE.)	115	
TOTAL	115	
X0322672 SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED	FT.	
11TH AVENUE		
LT. STA. 1+22 TO 3+07	185	
TOTAL	185	
X0322923 SEGMENTAL CONCRETE BLOCK WALL	S.F.	
11TH AVENUE		
LT. STA. 1+85 TO 2+80	436	
OUTDOOR CLASSROOM	54	
TOTAL	490	
X0323190 DUCTILE IRON WATER MAIN TEE, 12" X 12"	EACH	
11TH AVENUE		
13' RT. STA. 4+92	1	
TOTAL	1	
X0324445 DUCTILE IRON WATER MAIN FITTINGS 8" 22.5 DEGREE BEND	EACH	
11TH AVENUE		
8' LT. STA. 0+86	1	
TOTAL	1	
X0324928 VALVE GATE, 6" MJRW & BOX	EACH	
11TH AVENUE		
12' RT. STA. 5+40	1	
TOTAL	1	
X4200400 PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB	S. Y.	
11TH AVENUE		
STA. 1+07.60 TO 6+23.92	1,608.4	
37TH STREET		
STA. 9+91.60 TO 11+00.04	351.6	
TOTAL	1,960.0	
VALVE GATE, 4" MJRW & BOX	EACH	
11TH AVENUE		
12' RT. STA. 5+42.5	1	
TOTAL	1	
TAP & CORPORATION VALVE, 1 1/2"	EACH	
11TH AVENUE		
13' RT. STA. 4+92 (FOR TESTING)	1	
TOTAL	1	

CRUSHED STONE TRENCH FOUNDATION	C. Y.	
FOR WATER MAIN INSTALLATION AS NEEDED		20
TOTAL		20
SANITARY SEWER SERVICE CONNECTION REPAIR	EACH	
11TH AVENUE		
RT. STA. 1+06	1	
RT. STA. 1+85	1	
37TH STREET		
LT. STA. 10+55	1	
TOTAL		3
WOOD STAIRS	EACH	
NATURE TRAIL		
STA. 202+50 TO 202+76	130	
TOTAL		130

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT	EARTHWORK BALANCE
	C. Y.	C. Y.	C. Y.	C. Y.
11TH AVENUE	1055	791	90	+701
37TH STREET	185	139	4	+135
MULTI-USE PATH	664	498	388	+110
NATURE TRAIL	76	57	152	-95
TOTAL	1,980	1,485	634	+851
* ADJUSTED FOR SHRINKAGE FACTOR OF 25%				

PLOT DATE: 11/15/11
 FILE NAME: 111111.DWG
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: J. ROBERTS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. 1"=10'
HORIZ. 1"=40'

DATE: _____ DRAWN BY: _____
CHECKED BY: _____