CONTRACT NO. 85427

Route No.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		Rock Island	112	36
Sta. 200+00		To Sta. 205+00		
FED. ROAD DIST. NO. 7		ILLINOIS		

SCALE: 1" = 30'

10TH AVENUE

PROPOSED PERMANENT EASEMENT

PROPOSED OUTDOOR CLASSROOM (SEE OUTDOOR CLASSROOM LAYOUT & DETAILS)

EXISTING 18" CMP

POND

EXISTING 12" CMP

PROPOSED 4' NATURE TRAIL

STA: 204+71.54
31.00' RT

STA: 203+38.48
25.43' RT

POND

PROPOSED RETAINING WALL (TYP.)

PROPOSED 15" CMP. (SEE CROSS SECTION)

STA: 201+94.05
23.72' RT

EXISTING 12" CMP.

STA: 204+82.37
22.85' LT

STA: 203+26
24.41' LT

PROPOSED 15" CMP (SEE DRAINAGE & LAND REST. DETAILS)

STA: 201+81.26
26.19' LT

STA: 200+15.11
20.79' RT

EXISTING BIKE PATH

END PATH
STA. 205+00

BACKFILL RAVINE

STA: 202+64.92
37.6' LT

EXISTING 15" CMP.

EXISTING 6" CMP

POND

WESTERLIN RESIDENCE HALL

PROPOSED PERMANENT EASEMENT

EXISTING 30" CMP

BEGIN PATH
STA. 200+00

LEGEND

- EXISTING TREE
- TREE TO BE REMOVED
- LIGHT POLE

8' (WALL HT. OVER 4')
16' (WALL HT. UNDER 4')
EQUAL EQUAL
A
STAGGER DEADMAN EVERY OTHER COURSE
A

8x8 TIMBER
DREDGE LINE
4'-0"
TYPICAL DEADMAN

SECTION A-A

TYPICAL RETAINING WALL ELEVATION

NATURE TRAIL SITE PLAN

DESIGNED	MHM
CHECKED	JBF
DRAWN	RAP
CHECKED	JBF