SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: X020-2A

ITEM NO.	CODE NO.	ITEM	UNIT	QUANTITY
1	20200410*	EARTH EXCAVATION (SPECIAL)	CU YD	71
2	25000900*	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.04
3	35101400	AGGREGATE BASE COURSE, TYPE B	TON	28
4	40600100*	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	48
5	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	260
6	40800050*	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	73
7	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,392
8	42400800	DETECTABLE WARNINGS	SQ FT	16
9	50102400	CONCRETE REMOVAL	CU YD	34.7
10	50300100	FLOOR DRAINS	EACH	14
11	50300255	CONCRETE SUPERSTRUCTURES	CU YD	22.1
12	50300260	BRIDGE DECK GROOVING	SQ YD	444
13	50300300	PROTECTIVE COAT	SQ YD	465
14	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
15	50500715*	JACK AND REMOVE EXISTING BEARINGS	EACH	24
16	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7,820
17	51500100	NAME PLATES	EACH	1
18	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	24
19	59000200	EPOXY CRACK INJECTION	FOOT	143
20	60611600*	COMBINATION CONCRETE CURB AND GUTTER, SPECIAL	FOOT	258
21	67100100	MOBILIZATION	L SUM	1
22	70101700*	TRAFFIC CONTROL AND PROTECTION	L SUM	1
23	70300100*	SHORT-TERM PAVEMENT MARKING	FOOT	390
24	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	390
25	X0325303*	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	166
26	X0325305*	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	2
27	Z0006110*	BRIDGE DECK MICROSILICA CONCRETE OVERLAY	SQ YD	464
28	Z0006150*	BRIDGE DECK HYDRO-SCARIFICATION	SQ YD	422
29	Z0073500*	TEMPORARY SUPPORT SYSTEM	L SUM	1

*INDICATES SPECIAL PROVISION

Revised 6-2-08

S:/STRUCT/1093D07CityofRockFalls/COVERETC.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -	WILLETT, HOFMANN & ASSOCIATES, INC CONSULTING ENGINEERS DIXON, IL	SUMMARY OF QUANTITIES	F.A. RTE. 5560	SECTION 01-00125-00-BR	COUNTY WHITESIDE	TOTAL SHEETS 14 / SHEET NO. 2
		DRAWN -	REVISED -			CITY OF ROCK FALLS		CONTRACT NO. 85438	
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT	
	PLOT DATE = $DATE$	DATE -	REVISED -						