

SCHEDULES & GENERAL NOTES

LOCATION	EARTH EXCAVATION (SPECIAL)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
DIXON AVE	71	53	6	47

SEEDING, CLASS 1 (SPECIAL)		
STATION	ACRE	REMARKS
DIXON AVE 17+73.34 - 21+81.47	0.04	
PROJECT TOTAL	0.04	

AGGREGATE BASE COURSE, TYPE B		
STATION	TON	REMARKS
DIXON AVE RT 17+73.34 - 17+90.42	3	6"
RT 18+19.26 - 19+22.42	16	6"
LT 19+22.42 - 19+52.42	3	6"
RT 20+47.58 - 20+77.58	3	6"
LT 20+47.58 - 20+77.58	3	6"
PROJECT TOTAL	28	

BITUMINOUS MATERIALS (PRIME COAT)		
STATION	GALLON	REMARKS
DIXON AVE RT 17+73.34 - 17+90.42	2	.4 GAL/S.Y. OVER AGG
RT 17+73.34 - 17+90.42	1	.1 GAL/S.Y. OVER BIT
RT 18+19.26 - 19+22.42	3	.1 GAL/S.Y. OVER BIT
RT 18+19.26 - 19+22.42	11	.4 GAL/S.Y. OVER AGG
LT 19+22.42 - 19+52.42	1	.4 GAL/S.Y. OVER AGG
19+22.42 - 19+52.42	14	.1 GAL/S.Y. OVER BIT
20+47.58 - 20+77.58	14	.1 GAL/S.Y. OVER BIT
RT 20+47.58 - 20+77.58	1	.4 GAL/S.Y. OVER AGG
LT 20+47.58 - 20+77.58	1	.4 GAL/S.Y. OVER AGG
PROJECT TOTAL	48	

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
STATION	SQ YD	REMARKS
DIXON AVE 19+22.42 - 19+52.42	130	1 1/4" - 2"
20+47.58 - 20+77.58	130	1 1/4" - 2"
PROJECT TOTAL	260	

INCIDENTAL HOT-MIX ASPHALT SURFACING		
STATION	TON	REMARKS
DIXON AVE RT 17+73.34 - 17+90.42	6	15"
RT 18+19.26 - 19+22.42	23	15"
RT 19+22.42 - 19+52.42	3	15"
LT 19+22.42 - 19+52.42	3	15"
RT 20+47.58 - 20+77.58	3	15"
LT 20+47.58 - 20+77.58	3	15"
19+22.42 - 19+52.42	16	2"
20+47.58 - 20+77.58	16	2"
PROJECT TOTAL	73	

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		
STATION	50 FT	REMARKS
DIXON AVE RT 17+73.34 - 17+81.67	88	5'
RT 18+22.05 - 19+52.42	653	5'
RT 20+47.58 - 21+81.47	671	5'
PROJECT TOTAL	1,392	

DETECTABLE WARNINGS		
STATION	50 FT	REMARKS
DIXON AVE 17+86	8	2'x4'
18+24	8	2'x4'
PROJECT TOTAL	16	

COMBINATION CONCRETE CURB & GUTTER, SPECIAL		
STATION	FOOT	REMARKS
DIXON AVE RT 17+73.34 - 17+90.42	26	
RT 18+19.26 - 19+47.42	137	
LT 19+22.42 - 19+52.42	30	
RT 19+47.42 - 19+52.42	5	6" - 10.2" BACK OF CURB
RT 20+47.58 - 20+52.58	5	6" - 10" BACK OF CURB
RT 20+52.58 - 20+77.58	25	
LT 20+47.58 - 20+77.58	30	
PROJECT TOTAL	258	

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
DIXON AVE LT 19+37.42 - 20+67.42	40	WHITE LINE
RT 19+37.42 - 20+67.42	40	WHITE LINE
19+22.42 - 20+77.58	310	DOUBLE YELLOW
PROJECT TOTAL	390	

PAINT PAVEMENT MARKING LINE 4"		
STATION	FOOT	REMARKS
DIXON AVE LT 19+37.42 - 20+67.42	40	WHITE LINE
RT 19+37.42 - 20+67.42	40	WHITE LINE
19+22.42 - 20+77.58	310	DOUBLE YELLOW
PROJECT TOTAL	390	

GENERAL NOTES

THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKS, SECTION OR SUBSECTION MONUMENTS ENCOUNTERED, UNTIL AN OWNER OR AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. ANY PROPERTY MARKS, SECTION OR SUBSECTION MONUMENTS UNLESS REFERENCED, DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.

ALL TELEPHONE AND ELECTRIC POLES, GAS PIPES, ETC. IN THE WAY OF THE IMPROVEMENT SHALL BE MOVED BY THE UTILITIES PRIOR TO CONSTRUCTION AND SHALL NOT BE INCLUDED IN THE CONTRACT. THE CONTRACTOR SHALL NOTIFY THE RESPECTIVE UTILITIES TO MAKE THE NECESSARY ADJUSTMENTS PRIOR TO THIS CONSTRUCTION.

THE FINAL TOP 4" OF SOIL IN ANY AREA DISTURBED BY THE CONTRACTOR MUST BE ABLE TO SUPPORT VEGETATION.

EXISTING STREET SIGNS AND TRAFFIC SIGNS THAT ARE WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED AND RESET BY THE CONTRACTOR. COST OF REMOVING AND RESETTING SHALL BE INCIDENTAL TO EARTH EXCAVATION (SPECIAL).

WHERE THE PROPOSED CONSTRUCTION MEETS AN EXISTING BITUMINOUS SURFACE, OR WHERE SAWING IS NOT STATED ON THE PLANS, THE EXISTING SURFACE SHALL BE SAWED IN A NEAT, STRAIGHT LINE. COST OF SAWING TO BE INCLUDED IN THE CONTRACT UNIT PRICE PER UNIT OF EARTH EXCAVATION (SPECIAL).

PLAN
 SURVEYED BY
 DATE
 CHECKED BY
 DATE
 NOTE BOOK NO.
 FILE NO.

PROFILE
 SURVEYED BY
 DATE
 CHECKED BY
 DATE
 NOTE BOOK NO.
 FILE NO.

S:\STRUCT\1093D07C\tyofRockFalls\COVERETC.DGN

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	WILLETT, HOFMANN & ASSOCIATES, INC CONSULTING ENGINEERS DIXON, IL	SCHEDULES & GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			5560	D1-00125-00-BR	WHITESIDE	294	4
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CITY OF ROCK FALLS			CONTRACT NO. 05435	
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT

Revised 6-2-08