| ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| FAS 666 | 99-00080-00-RP | DOUGLAS | 279 | 5 |
| FED.ROAD DIST.NO. ... | ILLINOIS | PROJECT | C-95-323-07 | |

## PAVEMENT SCHEDULE

| STATION | TO | STATION | AREA (SQ YD) | LENGTH (FOOT) | 30200650 PROCESSING MODIFIED SOIL 12" (SQ YD) | 30201500 LIME 6% (TON) | 31100100 SUB-BASE GRANULAR MATL TYPE A (TON) | 35100100 AGGREGATE BASE COURSE TYPE A (TON) | 35600900 HMA BASE COURSE WIDENING (TON) | 40300100 BITUMINOUS MATERIALS (PRIME COAT) MC-30 @ 0.4 GAL/SYD (GALLON) | 40300300 BITUMINOUS MATERIALS (COVER & SEAL COATS) CRS-2 @ 0.4 GAL/SYD (GALLON) | 40300500 COVER COAT AGGREGATE CA-14 25 LB/SQ YD (TON) | 40300600 SEAL COAT AGGREGATE (CA-16) 25 LB/SQ YD (TON) | 40600100 BITUMINOUS MATERIALS (PRIME COAT) (GALLON) | 40600625 LEVEL BINDER (MACHINE METHOD) N50 (TON) | 40600982 HMA SURFACE REMOVAL BUTT JOINT (SQ YD) | 40603080 HMA BINDER COURSE IL-19.0, N50 (TON) | 40603310 HMA SURFACE COURSE MIX "C" N50 (TON) | 40701801 HMA PAVEMENT (FULL DEPTH) 6" (SQ YD) | 40701831 HMA PAVEMENT (FULL DEPTH) 7 1/2" (SQ YD) | 48101200 AGGREGATE SHOULDERS TYPE B (TON) | 48203105 HMA SHOULDERS (SPECIAL) (TON) | 60605000 COMBINATION CURB & GUTTER TYPE B-6.24 (F-OOT) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | CH-11 (200N) | | | | | | | | | | | | | | | | | | | | | |
| 21+00.00 | | 56+18.99 | 8601.973 | 3518.99 | 16812.9 | 378.3 | 2167.7 | | | 2658.8 | 5317.6 | 83.1 | 83.1 | 430.1 | | | | | 2658.8 | | | | |
| 56+18.99 | | 56+41.34 | 54.63578 | 22.35 | 106.8 | 2.4 | 6.9 | | | 8.4 | 16.9 | 0.3 | 0.3 | 2.7 | | | | | 8.4 | | | | |
| 56+41.34 | | 58+30.49 | 462.3667 | 189.15 | 903.7 | 20.3 | | | | | | | | 23.1 | | | | | 0.0 | | | | |
| 58+30.49 | | 58+52.76 | 54.43778 | 22.27 | 106.4 | 2.4 | 6.9 | | | 8.4 | 16.8 | 0.3 | 0.3 | 2.7 | | | | | 8.4 | | | | |
| 58+52.76 | | 87+51.84 | 7086.64 | 2899.08 | 13851.2 | 311.7 | 1785.8 | | | 2190.4 | 4380.8 | 68.5 | 68.5 | 354.3 | | | | | 2190.4 | | | | |
| 87+51.75 | | 109+00.00 | 5251.278 | 2148.25 | 10263.9 | 230.9 | 1323.3 | | | 1623.1 | 3246.2 | 50.7 | 50.7 | 262.6 | | | | | 5251.3 | | | | |
| 109+00.00 | | 109+03.67 | 8.97 | 3.7 | 17.5 | 0.4 | 2.3 | | | 2.8 | 5.5 | 0.1 | 0.1 | 0.4 | | | | | | 9.0 | | | |
| 109+03.67 | | 109+42.25 | 95.04 | 38.9 | 185.8 | 4.2 | 12.0 | | | 14.7 | 29.4 | 0.5 | 0.5 | 4.8 | | | | | | 95.0 | | | |
| 109+42.55 | | 110+47.37 | 256.23 | 104.8 | 500.8 | 11.3 | | | | | | | | 12.8 | | | | | | 256.2 | | | |
| 110+47.37 | | 110+58.71 | 27.72 | 11.3 | 54.2 | 1.2 | 3.5 | | | | | | | 1.4 | | | | | | 27.7 | | 3.6 | 11.3 |
| 110+58.71 | | 116+61.28 | 1472.95 | 602.6 | 2878.9 | 64.8 | 198.8 | | | | | | | 73.6 | | | | | | 1472.9 | | 191.2 | 1205.1 |
| 116+61.28 | | 116+78.30 | 41.60 | 17.0 | 81.3 | 1.8 | 5.6 | | | 6.4 | 12.9 | 0.2 | 0.2 | 2.1 | | | | | | 41.6 | | 5.4 | 17.0 |
| 116+78.30 | | 117+25.00 | 114.16 | 46.7 | 223.1 | 5.0 | 28.8 | | | 35.3 | 70.6 | 1.1 | 1.1 | 5.7 | | | | | | 114.2 | | | |
| 117+25.00 | | 149+06.66 | 7777.39 | 3181.7 | 15201.3 | 342.0 | 1959.9 | | | 2403.9 | 4807.8 | 75.1 | 75.1 | 388.9 | | | | | 7777.4 | | | | |
| 149+06.66 | | 150+72.52 | 405.64 | 165.9 | 792.4 | 17.8 | 51.1 | | | 62.7 | 125.3 | 2.0 | 2.0 | 20.3 | | | | | 405.4 | | | | |
| 150+72.52 | | 161+72.00 | 2687.62 | 1099.5 | 5253.1 | 118.2 | 677.5 | | | 830.7 | 1661.4 | 26.0 | 26.0 | 134.4 | | | | | 2687.6 | | | | |
| 163+04.00 | | 164+81.00 | 432.67 | 177.0 | 845.7 | 19.0 | 54.5 | | | 66.9 | 133.7 | 2.1 | 2.1 | 21.6 | | | | | 432.7 | | | | |
| 164+81.00 | | 229+81.61 | 15890.38 | 6500.6 | 31058.5 | 698.8 | 4004.4 | | | 4911.6 | 9823.1 | 153.5 | 153.5 | 794.5 | | | | | 15890.4 | | | | |
| 229+81.61 | | 230+78.65 | 237.21 | 97.0 | | | | | | | | | | 11.9 | 13.3 | | | 16.6 | | | | | |
| 230+78.65 | | 232+00.65 | 298.22 | 122.0 | | | | | | | | | | 14.9 | 16.7 | 123.0 | | 20.9 | | | 25.3 | | |
| | | FRONTAGE ROAD (50 EAST) | | | | | | | | | | | | | | | | | | | | | |
| 00+11.00 | | 00+46.58 | 182.76 | 35.6 | | | | 64.0 | | | | | | 9.1 | | | 8.5 | 12.8 | | | | | |
| 00+46.58 | | 01+41.97 | 272.77 | 95.4 | | | | 95.5 | | | | | | 13.6 | | | 22.7 | 19.1 | | | | | |
| | | 100 EAST | | | | | | | | | | | | | | | | | | | | | |
| 203+55.33 | | 204+84.59 | 661.67 | 129.3 | | | | 428.6 | | | | | | 33.1 | | | 30.8 | 46.3 | | | 12.5 | | |
| 205+06.59 | | 206+71.59 | 742.56 | 165.0 | | | | 483.2 | | | | | | 37.1 | | | 39.3 | 52.0 | | | 14.0 | | |
| | | 200 EAST | | | | | | | | | | | | | | | | | | | | | |
| 304+28.74 | | 305+48.99 | 538.00 | 120.3 | | | | 360.1 | | | | | | 26.9 | | | 28.6 | 37.7 | | | 8.2 | | 69.0 |
| 305+70.99 | | 306+91.70 | 537.78 | 120.7 | | | | 357.8 | | | | | | 26.9 | | | 28.7 | 37.6 | | | 7.3 | | 93.0 |
| | | 275 EAST | | | | | | | | | | | | | | | | | | | | | |
| 405+71.00 | | 406+92.03 | 486.11 | 121.0 | | | | 320.1 | | | | | | 24.3 | | | 28.8 | 34.0 | | | 11.5 | | |
| | | 300 EAST | | | | | | | | | | | | | | | | | | | | | |
| 129+50.00 | | 130+81.93 | 318.11 | 131.9 | | | | 248.9 | | | | | | 15.9 | | | 31.4 | 22.3 | | | 23.9 | | |
| 130+81.93 | | 131+88.99 | 600.89 | 258.0 | | | | 416.9 | | | | | | 30.0 | | | 61.4 | 42.1 | | | 22.1 | | |
| | | 425 EAST | | | | | | | | | | | | | | | | | | | | | |
| 49+50.00 | | 50+66.73 | 396.00 | 116.7 | | | | 28.2 | 9.9 | | | | | 19.8 | 38.8 | 123.0 | | 33.3 | | | 6.0 | | |
| 50+88.73 | | 52+00.00 | 394.00 | 111.3 | | | | 25.1 | 9.4 | | | | | 19.7 | 38.6 | 123.0 | | 33.1 | | | 11.5 | | |
| | | SUBTOTAL | | | 99137.5 | 2230.6 | 12288.7 | 2828.4 | 19.3 | 14824.1 | 29648.2 | 463.3 | 463.3 | 2819.4 | 107.4 | 369.0 | 280.2 | 407.7 | 37310.8 | 2016.7 | 142.2 | 200.2 | 1395.5 |
| | | TOTAL QUANTITY | | | 99138.0 | 2231.0 | 12289.0 | 2828.0 | 19.0 | 14824.0 | 29648.0 | 463.0 | 463.0 | 2819.0 | 107.0 | 369.0 | 280.0 | 408.0 | 37311.0 | 2017.0 | 142.0 | 200.0 | 1396.0 |

PREPARED BY: JEC
CHECKED BY: GD

3/11/2008

## STORM SEWER SCHEDULE

| PIPE RUN ID | STRUCTURE * | TO | STRUCTURE * | LENGTH CENTER TO CENTER STRUCTURE (FOOT) | 20800150 TRENCH BACKFILL (CU YD) | 55019500 STORM SEWER TY 1, RCCP CLASS IV 12" (FOOT) | 55019600 STORM SEWER TY 1, RCCP CLASS IV 15" (FOOT) | 55019700 STORM SEWER TY 1, RCCP CLASS IV 18" (FOOT) | 60101705 PIPE DRAINS 6" (SPECIAL) (FOOT) | 60101905 PIPE DRAINS 10" (SPECIAL) (FOOT) | 60102005 PIPE DRAINS 12" (SPECIAL) (FOOT) | 60102105 PIPE DRAINS 15" (SPECIAL) (FOOT) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | A-1 | | A-2 | 468.0 | | | | | | | | 468 |
| 2 | A-2 | | A-3 | 163.9 | 150.00 | | 163.9 | | | | | |
| 3 | A-3 | | A-4 | 1337.1 | | | | | | | 1337.1 | |
| 4 | A-4 | | A-5 | 640.3 | | | | | 640.3 | | | |
| 5 | A-5 | | A-6 | 700.0 | | | | | 700 | | | |
| 6 | A-6 | | A-7 | 275.8 | | | | | 275.8 | | | |
| 7 | A-7 | | A-8 | 134.1 | 48.64 | 134.10 | | | | | | |
| 8 | A-8 | | A-9 | 1349.9 | | | | | | 1349.9 | | |
| 9 | A-9 | | A-10 | 591.6 | | | | | | 591.6 | | |
| 10 | B-1 | | B-2 | 1375.6 | | | | | | | | |
| 11 | C-1 | | C-2 | 152.5 | 59.40 | 152.50 | | | | | | |
| 12 | C-2 | | C-3 | 248.0 | 198.40 | 248.00 | | | | | | |
| 13 | C-3-1 | | C-3 | 42.3 | 33.86 | 42.33 | | | | | | |
| 14 | C-3 | | C-4 | 250.0 | 200.00 | 250.00 | | | | | | |
| 15 | C-4-1 | | C-4 | 42.3 | 33.86 | 42.33 | | | | | | |
| 16 | C-4 | | C-5 | 249.7 | 104.00 | 249.69 | | | | | | |
| 17 | C-5 | | C-6 | 349.5 | | | | | | | 349.5 | |
| 18 | C-6 | | C-7 | 350.6 | | | | | | | 350.6 | |
| 19 | C-7 | | C-8 | 1390.0 | | | | | | | 1390 | |
| 20 | C-8 | | C-9 | 1750.0 | | | | | | | 1750 | |
| 21 | C-9 | | C-10 | 583.3 | | | | | | | 583.3 | |
| 22 | D-1 | | D-2 | 166.0 | 68.84 | | | 166 | | | | |
| 23 | D-2 | | D-3 | 698.5 | | | | | | | | 698.5 |
| 24 | D-3 | | D-4 | 750.1 | | | | | | | | 750.1 |
| 25 | D-4 | | D-5 | 1149.9 | | | | | | | 1149.9 | |
| 26 | D-5 | | D-6 | 527.9 | | | | | | | 527.9 | |
| 27 | D-6 | | D-7 | 947.0 | | | | | | | 947 | |
| 28 | A-7 | | B-2 | 71.7 | 34.20 | | | | | | | |
| 29 | B-2 | | E-1 | 31.5 | | | | | | | | |
| 30 | E-1 | | E-2 | 149.7 | | | | | | | | |
| 31 | F-1 | | F-2 | 108.0 | | | | | | | | |
| 32 | S-1 | | EXIST | 10 | | | | | | | | |
| 33 | S-2 | | EXIST | 10 | | | | | | | | |
| 34 | S-3 | | EXIST | 25.2 | | | | | | | | |
| 35 | PLUG | | S-5 | 1678.5 | | | | | 1678.5 | | | |
| 36 | S-4 | | S-5 | 65.35 | 30.00 | | 65.35 | | | | | |
| 37 | S-5 | | EXIST | 118.33 | 30.00 | | 118.33 | | | | | |
| | | | | SUBTOTAL | 991.2041 | 1118.95 | 347.58 | 166 | 3294.6 | 1941.5 | 8385.3 | 1916.6 |
| | | | | TOTAL QUANTITY | 992 | 1119 | 348 | 166 | 3295 | 1942 | 8386 | 1917 |

PREPARED BY: JEC
CHECKED BY: GD

3/11/2008

# SCHEDULES

| Revisions | | | Surveyed: DLE | FAS ROUTE 666 (CH 11) DOUGLAS COUNTY, ILLINOIS |
|---|---|---|---|---|
| No. | DATE | INITIALS | Designed: JEC | |
| 1 | | | Drawn: JEC | |
| 2 | | | Checked: --- | DOUGLAS COUNTY HIGHWAY DEPARTMENT TUSCOLA, ILLINOIS |
| 3 | | | Approved: JEC | |
| 4 | | | | |
| 5 | | | | |
| 6 | | | | |
| 7 | | | | |
| Job No.: NA | | | Date: 1/08 | |