

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 666	99-00080-00-RP	DOUGLAS	279	8
FED. ROAD DIST. NO. ...	ILLINOIS	PROJECT	C-95-323-07	

PAVEMENT MARKING SCHEDULE												
STATION	TO STATION	LENGTH (FOOT)	78000200		78000650		78005110		78100100		78100105	
			THERMOPLASTIC PAVEMENT MARKING - 4" LINE WHITE (FOOT)	THERMOPLASTIC PAVEMENT MARKING - 4" LINE YELLOW (FOOT)	THERMOPLASTIC PAVEMENT MARKING - 24" LINE WHITE (FOOT)	EPOXY PAVEMENT MARKING - LINE 4" YELLOW (FOOT)	EPOXY PAVEMENT MARKING - LINE 4" WHITE (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (TWO-WAY AMBER) (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (GRID) (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (GRID) (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (GRID) (EACH)	
CH 11 (2000)												
21+00.00	161+72.00	14072	28144	5628.8			264	52.8	180		2	
161+72.00	161+04.00	137										
163+04.00	228+41.47	6537.47	13074.94	2614.988					82			
228+41.47	229+91.47	150	300	300	15.25				4			
230+71.47	232+21.48	150.01	300.02	300.02	15.72				4			
100E												
203+95.33	204+71.09	115.76	373	231.52	37.04							
205+20.09	206+71.59	151.5	450	303	37.73							
200E												
304+28.66	305+35.49	106.83	327	213.66	29.51							
305+84.49	306+91.70	107.21	336	214.42	29.39							
275E												
405+84.50	406+92.03	107.53	336	215.06	25.94							
300E												
129+75.14	131+75.14	200	566	400	38.08							
425E												
49+50.00	50+48.23	98.23	290	196.46	19.91							
51+07.23	52+42.28	135.05	280	270.1	22.29							
SUBTOTAL			44776.96	10888.028	270.86	264	52.8	270	2			
TOTAL QUANTITY			55665		271	317		270	2			

PREPARED BY: JEC
CHECKED BY: GD
3/5/2008

LANDSCAPING SCHEDULE															
STATION	TO STATION	AREA (SQ FT)	25000200					25000400		25000500		25000600		25100115	
			SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)				
21+00.00	57+35.48	114,000	2.62	235.54	235.54	235.54	2.62								
57+35.48	110+00.00	228,628	5.75	472.37	472.37	472.37	5.75								
110+00.00	150+00.00	168,768	3.87	348.69	348.69	348.69	3.87								
150+00.00	163+65.00	79,459	1.82	164.17	164.17	164.17	1.82								
163+65.00	230+31.61	331,594	7.61	685.11	685.11	685.11	7.61								
230+31.61	232+55.00	18,238	0.42	37.68	37.68	37.68	0.42								
SUBTOTAL			21.60	1943.57	1943.57	1943.57	21.60								
TOTAL QUANTITY			22	1944	1944	1944	22								

PREPARED BY: JEC
CHECKED BY: GD
3/5/2008

AIR CULVERT SCHEDULE																		
STATION	TRENCH BACKFILL (CU YD)	20800150		54213675		54214503		54214509		54214515		54207153		54207159		54207165		
		PRECAST REINFORCED CONC F.E.S. 30" (EACH)	PRECAST REINFORCED CONC F.E.S. 18" (EACH)	PRECAST REINFORCED CONC F.E.S. 24" (EACH)	PRECAST REINFORCED CONC F.E.S. 30" (EACH)	PIPE CULVERT TYPE 1, RCCP ELLIPTICAL, EQUIVALENT ROUND SIZE 18" (FOOT)	PIPE CULVERT TYPE 1, RCCP ELLIPTICAL, EQUIVALENT ROUND SIZE 24" (FOOT)	PIPE CULVERT TYPE 1, RCCP ELLIPTICAL, EQUIVALENT ROUND SIZE 30" (FOOT)	PIPE CULVERT TYPE 1, RCCP ELLIPTICAL, EQUIVALENT ROUND SIZE 36" (FOOT)									
30+90.14	14.15																	
50+56.47	11.52																	
56+50.00	11.12																	
204+62.81 (100 E)	18.83																	
205+28.37 (100 E)	18.75																	
71+50.00	12.47																	
88+12.03	12.03																	
107+50.00	14.67																	
122+11.27	11.71																	
138+94.01	14.31																	
405+95.62 (275 E)	14.30																	
131+58.85 (FAS 666)	49.91																	
178+50.30	20.50																	
50+41.8 (425 E)	52.25																	
51+10.25 (425 E)	57.50																	
SUBTOTAL		334.01	2	4	18	8	112	632	256									
TOTAL QUANTITY		335	2	4	18	8	112	632	256									

PREPARED BY: JEC
CHECKED BY: GD
3/5/2008

SURVEY MARKERS			
STATION	O/S	20301232	
		SURVEY MARKER VAULTS (EACH)	
30+85.20	21.46	RT	1
57+20.41	16.91	LT	1
83+14.23	14.33	RT	1
110+08.08	0.00	CL	1
136+90.25	0.00	CL	1
163+66.25	0.00	CL	1
190+53.33	12.63	RT	1
216+91.00	1.55	LT	1
SUBTOTAL			8
TOTAL QUANTITY			8

PREPARED BY: DLE
CHECKED BY: JEC
3/5/2008

SCHEDULES			
Revisions	Surveyed:	DLE	FAS ROUTE 666 (CH 11) DOUGLAS COUNTY, ILLINOIS
1	Designed:	JEC	
2	Drawn:	JEC	
3	Checked:	---	
4	Approved:	JEC	
5	Date:	1/08	
6	Job No.:	NA	
7	Date:	1/08	