

**SUMMARY OF QUANTITIES**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-57	00-00374-03-LS	CHAMPAIGN	21	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 91382				

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	UNIT	TOTAL QUANTITY
+ 21101615	TOPSOIL FURNISH AND PLACE, 4"	Y003	SQ YD	970
+ 25000210	SEEDING, CLASS 2A	Y003	ACRE	0.2
+ 25000400	NITROGEN FERTILIZER NUTRIENT	Y003	POUND	18
+ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	Y003	POUND	18
+ 25000600	POTASSIUM FERTILIZER NUTRIENT	Y003	POUND	18
+ 25100105	MULCH METHOD 1	Y003	ACRE	0.2
+ 25100635	HEAVY DUTY EROSION CONTROL BLANKET	Y003	SQ YD	217
+ 25200200	SUPPLEMENTAL WATERING	Y003	UNIT	10
50200100	STRUCTURE EXCAVATION	Y003	CU YD	121
50300225	CONCRETE STRUCTURES	Y003	CU YD	155.6
• 50800205	REINFORCEMENT BARS, EPOXY COATED	Y003	POUND	10820
• 50901755	PARAPET RAILING, SPECIAL	Y003	FOOT	539
51201400	FURNISHING STEEL PILES HP10X42	Y003	FOOT	833
51202305	DRIVING PILES	Y003	FOOT	833
51203400	TEST PILE STEEL HP10X42	Y003	EACH	3
+ 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	Y003	EACH	1
+ 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	Y003	EACH	1
67100100	MOBILIZATION	Y003	L SUM	1
+ 78201000	TERMINAL MARKER - DIRECT APPLIED	Y003	EACH	1
+ 80400100 <sup>5</sup>	ELECTRIC SERVICE INSTALLATION, SPECIAL	Y003	EACH	1
+ 81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	Y003	FOOT	354
+ 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	Y003	FOOT	108
+ 81021330	CONDUIT PUSHED, 2" DIA., PVC	Y003	FOOT	100
+ 81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" x 12" x 6"	Y003	EACH	1
<del>81400750</del>	<del>HANDHOLE, COMPOSITE CONCRETE</del>	Y003	EACH	<del>1</del>
+ 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND (XLP-TYPE USE), 1" DIA. POLYETHYLENE	Y003	FOOT	700
+ 81702450	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/C <sup>NO.</sup> X10	Y003	FOOT	1254
+ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	Y003	FOOT	1161
+ 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP-240 VOLT	Y003	EACH	1
+ A2002420	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2 1/2" CALIPER, BALLED AND BURLAPPED	Y003	EACH	12
+ D2015401	SHRUB, JUNIPERUS CHINENSIS 'KALLAY'S COMPACTA' (KALLAY COMPACT JUNIPER), 5 GALLON	Y003	EACH	84
+ X0325403	CONDUIT, FLEXIBLE NON-METALLIC, WEATHERPROOF, 2"	Y003	EACH	4
+ XX005856	MULCH - SHREDDED HARDWOOD BARK, 3" DEPTH	Y003	CU YD	40
+ XX006302	NEPETA X FAASSENII 'WALKERS LOW' (WALKERS LOW CATMINT)	Y003	EACH	1000
• Z0013798	CONSTRUCTION LAYOUT	Y003	L SUM	1
• Z0076600	TRAINEES	Y003	HOUR	
+ XX007293	PERENNIAL, FALLOPIA JAPONICA 'COMPACTA' (COMPACT FLEECE FLOWER), 1 GALLON	Y003	EACH	3480
+ XX007294	PERENNIAL, MISCANTHUS SINENSIS 'PURPURASCENS' (PURPLE SILVER GRASS), 2 GALLON	Y003	EACH	40

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	UNIT	TOTAL QUANTITY
+ X8250500 • <del>5000841</del>	LIGHTING UNIT X COMPLETE, SPECIAL	Y003	EACH	6
+ X0324390 • <del>5000842</del>	FLOOD LIGHTING UNIT B, COMPLETE	Y003	EACH	6
+ • <del>XX007298</del>	MASONRY COLUMN, LARGE	Y003	EACH	2
+ • <del>XX007299</del>	MASONRY COLUMN, SMALL	Y003	EACH	4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	Y003	EACH	2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	Y003	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	Y003	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	Y003	L SUM	1
+ 81018100	CONDUIT PUSHED, 3/4" DIA., GALVANIZED STEEL	Y003	FOOT	120

+ = SPECIALTY ITEMS

p:\011286\plans\sum\Summary of Quantities.dgn 3/24/2008

Revised 3/28/08

• SEE SPECIAL PROVISIONS

**Clawson**  
ENGINEERS

DESIGN FIRM REGISTRATION NO. 184-000450  
118 SOUTH CLINTON STREET SUITE 800 CHICAGO, IL 60661  
PHONE : 312.648.0900 FAX : 312.648.0204

REVISIONS	
NAME	DATE
RLH	3/18/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: As Noted      DRAWN BY SLD  
DATE: 01/04/08      CHECKED BY JTP