

SCHEDULES OF QUANTITIES

LIGHTING SCHEDULE

LOCATION	LIGHTING UNIT A - COMPLETE, SPECIAL X8250500 (EACH)	FLOOD LIGHTING UNIT B - COMPLETE X0324390 (EACH)	CONDUIT, FLEX. NON-METALLIC, WEATHERPRF, 2" (EACH)	CONDUIT IN TRENCH, 3/4" DIA. PVC (FOOT)	CONDUIT IN TRENCH, 2" DIA. PVC (FOOT)	CONDUIT PUSHED, 2" DIA. PVC (FOOT)	CONDUIT PUSHED, 3/4" DIA. GALVANIZED STEEL (FOOT)	JUNCTION BOX, 18" X 12" X 6" (EACH)	HANDHOLE, COMPOSITE CONCRETE (EACH)	TRENCH AND BACKFILL FOR ELECTRICAL WORK (FOOT)	UNIT DUCT (FOOT)	ELEC. CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/2" X 10" NO. (FOOT)	ELEC. SERVICE INSTALLATION, SPECIAL (EACH)	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP - 240 VOLT (EACH)
CURTIS 29+25RT	1	1												
CURTIS 29+25LT	1	1												
CURTIS 28+20RT	1	1		2.0					1					
CURTIS 28+20LT	1	1												
CURTIS 27+15RT	1	1												
CURTIS 27+15LT	1	1												
CURTIS 29+53LT			1		8.0					8.0				
CURTIS 29+53RT			1					1						
CURTIS 26+87LT			1											
CURTIS 26+87RT			1											
CURTIS 29+89LT TO 29+89RT						100.0						100.0		
CURTIS 29+53RT TO 29+89RT					50.0					50.0		50.0		
CURTIS 29+53LT TO 29+89LT					50.0					50.0		50.0		
CURTIS 29+53RT TO 35+60RT										700.0	700.0			
CURTIS 29+53RT TO 26+87RT												280.0		
CURTIS 29+53LT TO 26+87LT												280.0		
CURTIS 29+53RT TO 29+25RT				40.0						40.0		45.0		
CURTIS 29+53LT TO 29+25LT				50.0 40.0						50.0 40.0		45.0	55.0	
CURTIS 26+87RT TO 27+15RT				40.0						40.0		45.0		
CURTIS 26+87LT TO 27+15LT				40.0						40.0		45.0		
CURTIS 29+53RT TO 28+96RT				80.0	80.0		60.0			80.0		72.0		
CURTIS 28+96RT TO 28+36RT						60.0						60.0		
CURTIS 28+36RT TO 28+20RT				17.0	17.0					16.0 17.0		20.0		
CURTIS 28+20RT TO 28+20LT				145.0						145.0		150.0		
CURTIS 35+65RT													1	1
CURTIS 28+20LT TO 29+25LT				97.0						97.0		102.0		
CURTIS 28+96LT TO 28+36LT							60.0					60.0		
TOTALS	6	6	4	354.0	108.0	100.0	120.0	1	1	1161.0	700.0	1254.0	1	1
UNIT	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)
PAY ITEM	X8250500	X0324390	X0325403	81012200	81012600	81021330	81018100	81300800	81400730	81900200	81603035	81702450	80400105	82500510

D:\2008\1006\plans\sheet\Lighting_Sheets.dgn 3/27/08

Revised 3/28/08

DESIGN FIRM REGISTRATION
No. 184-000450
118 SOUTH CLINTON STREET
SUITE 600
CHICAGO, IL 60661
PHONE : 312.648.0800
FAX : 312.648.0804

REVISIONS	
NAME	DATE
RLH	3/18/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

LIGHTING SCHEDULE OF QUANTITIES

SCALE: As Noted DRAWN BY: RS
DATE: 01/04/08 CHECKED BY: MTP