

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00334-00-SW	MCLEAN	13	C1.1
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

PAY CODE	ITEMS	UNIT	QUANTITY
* 2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22
* 2020010	EARTH EXCAVATION	CU YD	110
* 2080015	TRENCH BACKFILL	CU YD	220
2800050	INLET AND PIPE PROTECTION	EACH	4
* 3110100	SUBBASE GRANULAR MATERIAL, TYPE B	TON	90
* 3530020	P.C.C. BASE COURSE 7"	SQ YD	260
* 4060330	HOT MIX ASPHALT SURF CRSE. MIX C, N50	TON	50
* 4230020	P.C.C. DRIVEWAY PAVEMENT, 6"	SQ YD	80
4240080	DETECTABLE WARNINGS	SQ FT	30
4400020	DRIVEWAY PAVEMENT REMOVAL	SQ YD	85
* 4400060	SIDEWALK REMOVAL	SQ FT	4,750
550A0340	STORM SEWER, CLASS A, TYPE 2, 12"	FOOT	60
550B0040	STORM SEWER, CLASS B, TYPE 1, 10"	FOOT	10
* 6022840	MANHOLES, SPECIAL	EACH	1
* 6023570	INLETS, TYPE A, TYPE 3 FRAME & GRATE	EACH	2
* 6025550	MANHOLES TO BE ADJUSTED	EACH	6
* 6026010	INLETS TO BE ADJUSTED	EACH	2
* 6026660	VALVE BOXES TO BE ADJUSTED	EACH	6
6710010	MOBILIZATION	L SUM	1
* 7010370	TRAFFIC CONTROL COMPLETE	L SUM	1
7280010	TELESCOPING STEEL SIGN SUPPORT	FOOT	48
8040010	ELECTRIC SERVICE INSTALLATION	EACH	1
8100060	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	275
8100100	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30
8101260	CONDUIT IN TRENCH, 2" PVC	FOOT	1,500
* 8140010	HANDHOLE (SPECIAL)	EACH	9
* 8170210	ELECTRICAL CABLE IN CONDUIT 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	3,920
* 8360010	LIGHT POLE FOUNDATION	EACH	7
* 7001379	CONSTRUCTION LAYOUT	L SUM	1
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2
* K1005481	SHREDDED BARK MULCH, 3"	SQ YD	1
* XX000133	BICYCLE RACKS	EACH	2
* XX005420	ULMUS PARVIFOLIA 'FRONTIER' (FRONTIER CHINESE ELM) 2-1/2 CAL	EACH	7
* XX005819	INLET TYPE A1, SPECIAL	EACH	1
* XX006429	SIDEWALK, SPECIAL	SQ FT	1
* X0324994	ORNAMENTAL PLANTER	EACH	4,750
* X0444100	BENCHES	EACH	16
* X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	9
* X5011100	CONCRETE FOUNDATION REMOVAL	EACH	2
X8250400	LIGHTING CONTROLLER, PEDESTAL MOUNT	EACH	1
	STRAWBERRY CANDY DAYLILY	EACH	36
* 10	LIGHT 445 WATT FLUORESCENT	EACH	2
	LIGHT 105 WATT FLUORESCENT	EACH	5
	COMPOST FURNISH AND PLACE, SPECIAL	CU YD	3

* SPECIAL PROVISION

REVISIONS	
NAME	DATE
ADDENDUM #1	5-21-08
REV. ADDENDUM #1	5-29-08

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 CITY OF BLOOMINGTON
 DOWNTOWN MAIN STREET BEAUTIFICATION
 FRONT STREET TO WASHINGTON STREET
 SCALE: VERT.
 HORIZ.
 DATE: 01-31-08
 DRAWN BY: DVH
 CHECKED BY: JGB

PLT SIZE = 11x17
 FILE NAME = 011111
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = MJB/BA