

| | | | | |
|---------------------|----------------|-----------|--------------------|-----------|
| ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| F.A.U. 7059 | 05-00155-00-RS | VERMILION | 97 | 3 |
| FED. ROAD DIST. NO. | | ILLINOIS | CONTRACT NO. | |
| | | | CONTRACT NO. 91386 | |

| SUMMARY OF QUANTITIES | | | |
|-----------------------|--|--------|-------|
| CODE # | ITEM | UNIT | TOTAL |
| # 20200100 | EARTH EXCAVATION | CU YD | 97 |
| # 20400800 | FURNISHED EXCAVATION | CU YD | 93 |
| # 20800150 | TRENCH BACKFILL | CU YD | 877.4 |
| ^ 25000900 | SEEDING, CLASS 1 (SPECIAL) | ACRE | 0.36 |
| # 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 144 |
| # 28000400 | PERIMETER EROSION BARRIER | FOOT | 674 |
| # 28000500 | INLET AND PIPE PROTECTION | EACH | 15 |
| # 28000510 | INLET FILTERS | EACH | 22 |
| # 31100300 | SUB-BASE GRANULAR MATERIAL, TYPE A 4" | SQ YD | 622 |
| # 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 632 |
| # 40600300 | AGGREGATE (PRIME COAT) | TON | 14 |
| # 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 665 |
| # 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 106 |
| # 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 176 |
| # 40600990 | TEMPORARY RAMP | SQ YD | 115 |
| # 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 651 |
| # 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 510 |
| # 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 34 |
| # 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 368 |
| # 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH | SQ YD | 31 |
| # 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ FT | 6978 |
| # 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 4654 |
| # 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 233 |
| # 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 2335 |
| # 44000600 | SIDEWALK REMOVAL | SQ FT | 7451 |
| # 44201325 | CLASS C PATCHES, TYPE I, 8 INCH | SQ YD | 25 |
| # 44201329 | CLASS C PATCHES, TYPE II, 8 INCH | SQ YD | 156 |
| # 44201333 | CLASS C PATCHES, TYPE III, 8 INCH | SQ YD | 121 |
| # 44201335 | CLASS C PATCHES, TYPE IV, 8 INCH | SQ YD | 201 |
| # 44213100 | PAVEMENT FABRIC | SQ YD | 322 |
| # 55019500 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12" | FOOT | 1171 |
| # 55019600 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15" | FOOT | 339 |
| # 55019700 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18" | FOOT | 222 |
| # 55019900 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24" | FOOT | 21 |
| # 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 2 |
| ^ 60224600 | RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 12 |
| ^ 60225400 | RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 |

| SUMMARY OF QUANTITIES | | | |
|-----------------------|---|-------|-------|
| CODE # | ITEM | UNIT | TOTAL |
| # 60236200 | INLETS, TYPE A, TYPE 8 GRATE | EACH | 5 |
| # 60236825 | INLETS, TYPE A, TYPE 11V FRAME AND GRATE | EACH | 4 |
| # 60236900 | INLETS, TYPE A, TYPE 12 FRAME AND GRATE | EACH | 2 |
| # 60240301 | INLETS, TYPE B, TYPE 8 GRATE | EACH | 1 |
| # 60240312 | INLETS, TYPE B, TYPE 11V FRAME AND GRATE | EACH | 5 |
| # 60255500 | MANHOLES TO BE ADJUSTED | EACH | 6 |
| # 60262900 | INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID | EACH | 1 |
| # 60500050 | REMOVING CATCH BASINS | EACH | 7 |
| # 60500060 | REMOVING INLETS | EACH | 7 |
| # 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 1606 |
| # 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 695 |
| # 60609200 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 | FOOT | 66 |
| # 67100100 | MOBILIZATION | L SUM | 1 |
| ^ 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 |
| # 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 732 |
| # 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 54 |
| * 70300625 | TEMPORARY PAINT PAVEMENT MARKING LINE 4" | FOOT | 1153 |
| * 70300660 | TEMPORARY PAINT PAVEMENT MARKING LINE 24" | FOOT | 30 |
| # 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 685 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 54 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 1153 |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 30 |
| ^ XX002998 | RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3V FRAME AND GRATE | EACH | 1 |
| ^ XX006974 | INLETS, TYPE B, TYPE 3V FRAME AND GRATE, SPECIAL | EACH | 2 |
| ^ XX006976 | INLETS, TYPE A, TYPE 3V FRAME AND GRATE, SPECIAL | EACH | 1 |
| ^ Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 |
| ^ Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 |

^ - SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

PLOT DATE: 3/12/2008 FILE NAME: 91386-4-shit-summer-1.dgn

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

HLR

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 07.0131.330 DATE: 3/11/08
 DESIGNED: L.F.S. CHECKED: DRAWN: TWK

SUMMARY OF QUANTITIES
 F.A.U. 7059
 SECTION 05-00155-00-RS
 WEST STREET GEORGETOWN
 VERMILION COUNTY