

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
608	97-00043-01-FP	SCOTT	11	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS PROJECT NO	SR-0608(111)		

PAVEMENT SCHEDULE

STATION TO STATION		EARTH EXCAVATION	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	AGGREGATE WEDGE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS, 8"
		CU YD	SQ YD	TON	GALLON	TON		SQ YD		TON		SQ YD
0+11.52	1+34.30	73.3	149.8		45.6	1.2		205.2		51.1	20.5	179.3
1+34.30	12+17.06				200.8	5.4				223.6	109.5	
12+17.06	125+35.00				1,968.8	52.5	3,276.3	233.3	3,917.8	2,337.2	3,437.4	
SIDEROADS										79.9		
ENTRANCES				88.9						100.7		
MAILBOX TURNOUTS										17.0		
TOTALS		73.3	149.8	88.9	2,215.2	59.1	3,276.3	438.5	3,917.8	2,809.5	3,567.4	179.3
USE		74	150	89	2,216	60	3,277	439	3,918	2,810	3,568	180

PAVEMENT MARKING SCHEDULE

STATION TO STATION		SIDE	DESCRIPTION	PAINT PAVEMENT MARKING		
				LINE - 5" (YELLOW)	LINE - 5" (WHITE)	24" STOP BAR (WHITE)
				FOOT		
0+11.52	1+34.30	RT & LT	EDGE LINES		373.6	
0+34.00		LT	STOP BAR			21.0
0+34.00	53+20.00	CL	SKIP-DASH	1,321.5		
1+34.30	123+45.00	RT & LT	EDGE LINES		24,421.4	
39+25.00	53+20.00	CL	EB NPZ	1,395.0		
53+20.00	95+10.00	CL	DOUBLE NPZ	4,190.0		
95+10.00	125+35.00	CL	SKIP-DASH	756.3		
95+10.00	109+50.00	CL	WB NPZ	1,440.0		
123+45.00		RT	STOP BAR			11.0
124+30.00		LT	STOP BAR			11.0
124+30.00	125+35.00	RT & LT	EDGE LINES		210.0	
124+30.00	125+35.00	CL	SKIP-DASH	26.3		
TOTALS				9,129.1	25,005.0	43.0
USE				34,135		43

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

COUNTY HIGHWAY 7  
SCHEDULES OF QUANTITIES

SCALE: VERT.  
DATE      HORIZ.

DRAWN BY TJD  
CHECKED BY JRB